

# SCHEDULES OF QUANTITIES

**50104600 CONCRETE RETAINING WALL REMOVAL**

| FOOT | LOCATION |     |         |         |
|------|----------|-----|---------|---------|
| 11   | LT       | STA | 44+36.7 | @ 34.5' |
| 11   | TOTAL    |     |         |         |

**54213663 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"**

| EACH | LOCATION |     |          |         |
|------|----------|-----|----------|---------|
| 1    | LT       | STA | 32+54.02 | @ 79.5' |
| 1    | LT       | STA | 44+27.23 | @ 52.1' |
| 2    | TOTAL    |     |          |         |

**550A0360 STORM SEWERS, CLASS A, TYPE 2 15"**

| FOOT | LOCATION  |     |         |           |
|------|-----------|-----|---------|-----------|
| 124  | 15.85' LT | STA | 31+38.3 | - 32+64.8 |
| 124  | TOTAL     |     |         |           |

**550A0380 STORM SEWERS, CLASS A, TYPE 2 18"**

| FOOT | LOCATION |     |         |  |
|------|----------|-----|---------|--|
| 8    | LT       | STA | 32+64.8 |  |
| 8    | LT       | STA | 32+64.8 |  |
| 14   | LT       | STA | 32+64.8 |  |
| 12   | LT       | STA | 32+64.8 |  |
| 14   | LT       | STA | 32+64.8 |  |
| 12   | LT       | STA | 44+27.2 |  |
| 20   | LT       | STA | 44+27.2 |  |
| 88   | TOTAL    |     |         |  |

**REMARKS**

Between Inlet, Special No 5 and MH 1 - See Plan Sheet  
 Between MH 1 and MH 2 - See Plan Sheet  
 Between MH 2 and MH 3 - See Plan Sheet  
 Between MH 3 and MH 4 - See Plan Sheet  
 Between MH 4 and Outfall - See Plan Sheet  
 Between Inlet, Special No 5 and MH - See Plan Sheet  
 Between MH and Outfall - See Plan Sheet

**55100900 STORM SEWER REMOVAL 18"**

| FOOT | LOCATION |     |         |  |
|------|----------|-----|---------|--|
| 37   | LT       | STA | 31+38.3 |  |
| 17   | LT       | STA | 44+27.2 |  |
| 54   | TOTAL    |     |         |  |

**55101200 STORM SEWER REMOVAL 24"**

| FOOT | LOCATION |     |         |  |
|------|----------|-----|---------|--|
| 42   | LT       | STA | 32+64.8 |  |
| 42   | TOTAL    |     |         |  |

**60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID**

| EACH | LOCATION |     |         |         |
|------|----------|-----|---------|---------|
| 1    | LT       | STA | 32+64.8 | @ 26.0' |
| 1    | LT       | STA | 32+64.8 | @ 36.5' |
| 1    | LT       | STA | 32+64.8 | @ 52.5' |
| 1    | LT       | STA | 32+64.8 | @ 68.1' |
| 1    | LT       | STA | 44+27.2 | @ 30.2' |
| 5    | TOTAL    |     |         |         |

**60242801 INLETS, SPECIAL, NO. 5**

| EACH | LOCATION |     |         |         |
|------|----------|-----|---------|---------|
| 1    | LT       | STA | 31+38.3 | @ 14.0' |
| 1    | LT       | STA | 32+64.8 | @ 14.0' |
| 1    | LT       | STA | 44+27.2 | @ 14.0' |
| 3    | TOTAL    |     |         |         |

**60255410 CATCH BASINS TO BE CLEANED**

| EACH | LOCATION |     |         |         |
|------|----------|-----|---------|---------|
| 1    | LT       | STA | 37+88.9 | @ 13.1' |
| 1    | RT       | STA | 39+87.3 | @ 13.0' |
| 1    | RT       | STA | 41+86.6 | @ 13.0' |
| 1    | RT       | STA | 46+20.8 | @ 15.8' |
| 1    | LT       | STA | 46+20.9 | @ 14.9' |
| 5    | TOTAL    |     |         |         |

**60500050 REMOVING CATCH BASINS**

| EACH | LOCATION |     |         |         |
|------|----------|-----|---------|---------|
| 1    | LT       | STA | 31+38.3 | @ 14.0' |
| 1    | LT       | STA | 32+64.8 | @ 14.0' |
| 1    | LT       | STA | 44+27.2 | @ 14.0' |
| 3    | TOTAL    |     |         |         |

**60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24**

| FOOT  | LOCATION |     |         |           |
|-------|----------|-----|---------|-----------|
| 144.5 | LT       | STA | 31+29.3 | - 32+73.8 |
| 18    | LT       | STA | 44+18.2 | - 44+36.2 |
| 163   | TOTAL    |     |         |           |