



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2010

SUBJECT: FAI Route 39 (I-39)  
Section (103-1, 103-2)RS  
Lee County  
Contract No. 64E97  
Item No. 316, June 11, 2010 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised sheets 9, 10, 16, 19, 21, 23 - 25, 32 - 37, 61, 62 & 92 - 127.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading 'Ted B. Walschleger', followed by 'P.E.' in a smaller font.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 1  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XZ191203	BR DK MIC C OVL 2 3/4	SQ YD	6,040.000				
X0300136	BR APPROACH SHLD REM	SQ YD	328.000				
X0320157	CLEAN UNDERDR OUTLET	EACH	856.000				
X0320547	REM & REIN END SECT	EACH	1.000				
* X0322729	MATL TRANSFER DEVICE	TON	223,254.000				
X0323095	TYPE 1 FRAME CLOS LID	EACH	1.000				
X0325303	STR REP CON DP OVER 5	SQ FT	7.000				
X0325305	STR REP CON DP = < 5	SQ FT	190.000				
X0325519	DRAIN FOR AGG BSE CSE	SQ YD	420.000				
X0326682	UPGRAD EX WEATHER STA	L SUM	1.000				
X0329911	GRAD SHAP MED CROSS	EACH	9.000				
X0931400	INLET BOX ADJ SPL	EACH	16.000				
X4210307	WF BEAM TM JT REP SPL	EACH	8.000				
X7030068	GRV RCSD PVT LT N SYM	SQ FT	85.000				
X7030070	GRV RCSD PVT MRKG 5	FOOT	453,507.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

Page 2  
6/1/2010

64E97

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE- -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7030074	GRV RCSD PVT MRKG 7	FOOT	51,735.000				
X7030076	GRV RCSD PVT MRKG 9	FOOT	11,704.000				
X7030078	GRV RCSD PVT MRKG 13	FOOT	1,870.000				
X7030090	GRV RCSD PVT MRKG 25	FOOT	384.000				
Z0005400	BREAKER-RUN CR STONE	TON	2,822.000				
Z0006204	BR DECK HY-SCAR 1/2	SQ YD	6,040.000				
Z0010555	DITCH CLEANING	FOOT	362.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0015500	DEBRIS REMOVAL	L SUM	1.000				
Z0016001	DECK SLAB REP (FD-T1)	SQ YD	68.000				
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	87.000				
Z0017100	DOWEL BARS	EACH	1,372.000				
Z0028415	GEOTECHNICAL REINF	SQ YD	1,402.000				
Z0028700	GRAN SUBGRADE REPL	CU YD	234.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER - 64E97

Page 3  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030350	IMP ATTN REL NRD TL3	EACH	4.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0075300	TIE BARS	EACH	2,950.000				
20200100	EARTH EXCAVATION	CU YD	15,960.000				
20800150	TRENCH BACKFILL	CU YD	214.000				
21400110	GRADING & SHAP DITCH	UNIT	119.000				
25000210	SEEDING CL 2A	ACRE	9.500				
25000400	NITROGEN FERT NUTR	POUND	828.000				
25000500	PHOSPHORUS FERT NUTR	POUND	828.000				
25000600	POTASSIUM FERT NUTR	POUND	828.000				
25000750	MOWING	ACRE	9.500				
25100630	EROSION CONTR BLANKET	SQ YD	43,500.000				
25100900	TURF REINF MAT	SQ YD	3,390.000				
28000250	TEMP EROS CONTR SEED	POUND	7,357.000				
28000305	TEMP DITCH CHECKS	FOOT	5,000.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER - 64E97

Page 4  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE- -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000400	PERIMETER EROS BAR	FOOT	50,000.000				
28000500	INLET & PIPE PROTECT	EACH	10.000				
28100103	STONE RIPRAP CL A2	SQ YD	300.000				
28100107	STONE RIPRAP CL A4	SQ YD	243.000				
28200200	FILTER FABRIC	SQ YD	243.000				
31100300	SUB GRAN MAT A 4	SQ YD	3,890.000				
31100910	SUB GRAN MAT A 12	SQ YD	18,358.000				
31200500	STAB SUBBASE HMA 4	SQ YD	14,145.000				
35100500	AGG BASE CSE A 6	SQ YD	3,140.000				
40600200	BIT MATLS PR CT	TON	810.700				
40600300	AGG PR CT	TON	4,252.000				
40600400	MIX CR JTS FLANGEWYS	TON	680.500				
40600645	LEV BIND MM N90	TON	1,922.000				
40600855	P LEV BIND MM N105	TON	38,965.000				
40600895	CONSTRUC TEST STRIP	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 5  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE- -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600985	PCC SURF REM BUTT JT	SQ YD	2,852.000				
40603245	P HMA BC IL19.0 N105	TON	70,343.000				
40603310	HMA SC "C" N50	TON	35,611.000				
40603370	HMA SC "E" N90	TON	3,003.000				
40603575	P HMA SC "E" N105	TON	50,669.000				
42001200	PAVEMENT FABRIC	SQ YD	900.000				
42001300	PROTECTIVE COAT	SQ YD	12,807.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	4,732.000				
42100300	CONT REINF PCC PVT 10	SQ YD	4,711.000				
42100345	CONT R PCC PVT 12 1/4	SQ YD	3,156.000				
42100900	PAVT REINFORCEMENT 10	SQ YD	4,711.000				
42100945	PAVT REINF 12 1/4	SQ YD	7,891.000				
42101080	WF BM TERM JT COM SPL	EACH	1.000				
44000157	HMA SURF REM 2	SQ YD	7,382.000				
44000198	HMA SURF REM VAR DP	SQ YD	4,588.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 6  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE- -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000700	APPROACH SLAB REM	SQ YD	4,724.000				
44002100	CONT REINF C PAVT REM	SQ YD	9,324.000				
44004250	PAVED SHLD REMOVAL	SQ YD	8,430.000				
* 44200553	CL A PATCH T2 10	SQ YD	675.000				
* 44200557	CL A PATCH T3 10	SQ YD	675.000				
* 44200559	CL A PATCH T4 10	SQ YD	8,100.000				
44200934	CL B PATCH T2 8	SQ YD	193.000				
44200942	CL B PATCH T3 8	SQ YD	85.000				
44200944	CL B PATCH T4 8	SQ YD	279.000				
44200970	CL B PATCH T2 10	SQ YD	182.000				
44200974	CL B PATCH T3 10	SQ YD	21.000				
44200976	CL B PATCH T4 10	SQ YD	514.000				
* 44213000	PATCH REINFORCEMENT	SQ YD	9,450.000				
* 44213200	SAW CUTS	FOOT	35,540.000				
44301200	ST REF CR CON TR B 24	FOOT	29,199.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER - 64E97

Page 7  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE- -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* 48100100	AGGREGATE SHLDS A	TON	54,532.000				
* 48203011	HMA SHOULDERS 3 1/2	SQ YD	350,662.000				
48203029	HMA SHOULDERS 8	SQ YD	2,248.000				
* DELETED							
48300300	PCC SHOULDERS 8	SQ YD	3,140.000				
48300705	PCC SHOULDERS 12 1/4	SQ YD	4,704.000				
50102400	CONC REM	CU YD	95.000				
50104650	SLOPE WALL REMOV	SQ YD	126.000				
50157300	PROTECTIVE SHIELD	SQ YD	3,676.000				
50300225	CONC STRUCT	CU YD	210.200				
50300255	CONC SUP-STR	CU YD	1,108.900				
50300260	BR DECK GROOVING	SQ YD	7,861.000				
50300300	PROTECTIVE COAT	SQ YD	8,335.000				
50500405	F & E STRUCT STEEL	POUND	44,020.000				
50500715	JACK & REM EX BEARING	EACH	98.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 8  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50501110	STRUCT STEEL REMOV	POUND	15,860.000				
50800205	REINF BARS, EPOXY CTD	POUND	277,330.000				
50800515	BAR SPLICERS	EACH	1,968.000				
51100100	SLOPE WALL 4	SQ YD	126.000				
52000110	PREF JT STRIP SEAL	FOOT	698.000				
52100010	ELAST BEARING ASSY T1	EACH	61.000				
52100020	ELAST BEARING ASSY T2	EACH	12.000				
52100520	ANCHOR BOLTS 1	EACH	196.000				
59000200	EPOXY CRACK INJECTION	FOOT	12.000				
60100060	CONC HDWL FOR P DRAIN	EACH	36.000				
60107600	PIPE UNDERDRAINS 4	FOOT	8,167.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	640.000				
60260100	INLETS ADJUST	EACH	6.000				
60262405	INLET ADJ N MI 604101	EACH	10.000				
60600605	CONC CURB TB	FOOT	1,936.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 9  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63000001	SPBGR TY A 6FT POSTS	FOOT	3,837.500				
63100085	TRAF BAR TERM T6	EACH	22.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	10.000				
63200310	GUARDRAIL REMOV	FOOT	4,717.000				
63300575	R&R RAIL ELEM EX GDRL	FOOT	650.000				
63500105	DELINEATORS	EACH	75.000				
63500310	REM & REIN DELINEATOR	EACH	654.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	388,340.000				
66502405	WOV W FENCE REM & RPL	FOOT	461.000				
66700305	PERM SURV MKRS T2	EACH	5.000				
67000400	ENGR FIELD OFFICE A	CAL MO	18.000				
67100100	MOBILIZATION	L SUM	1.000				
70100207	TRAF CONT-PROT 701402	EACH	4.000				
70100420	TRAF CONT-PROT 701411	EACH	16.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 10  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70100820	TRAF CONT-PROT 701451	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	85.000				
70300100	SHORT-TERM PAVT MKING	FOOT	79,254.000				
70300220	TEMP PVT MK LINE 4	FOOT	964,945.000				
70300240	TEMP PVT MK LINE 6	FOOT	103,471.000				
70300250	TEMP PVT MK LINE 8	FOOT	22,639.000				
70300260	TEMP PVT MK LINE 12	FOOT	3,680.000				
70300280	TEMP PVT MK LINE 24	FOOT	768.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	415,384.000				
70400100	TEMP CONC BARRIER	FOOT	6,925.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

64E97

Page 11  
6/1/2010

State Job # - C-92-103-10  
PPS NBR - 2-17400-0100  
County Name - LEE -  
Code - 103 - -  
District - 2 - -  
Section Number - (103-1, 103-2)RS

Project Number

Route

FAI 39

\* REVISED : MAY 28, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70400200	REL TEMP CONC BARRIER	FOOT	6,925.000				
78008300	POLYUREA PM T2 LTR-SY	SQ FT	81.000				
78008310	POLYUREA PM T2 LN 4	FOOT	453,507.000				
78008330	POLYUREA PM T2 LN 6	FOOT	51,735.000				
78008340	POLYUREA PM T2 LN 8	FOOT	11,704.000				
78008350	POLYUREA PM T2 LN 12	FOOT	1,870.000				
78008370	POLYUREA PM T2 LN 24	FOOT	384.000				
78100100	RAISED REFL PAVT MKR	EACH	3,294.000				
78100105	RAISED REF PVT MKR BR	EACH	58.000				
78200410	GUARDRAIL MKR TYPE A	EACH	82.000				
78200520	BAR WALL MKR TYPE B	EACH	64.000				
78201000	TERMINAL MARKER - DA	EACH	10.000				
78300100	PAVT MARKING REMOVAL	SQ FT	7,421.000				
78300200	RAISED REF PVT MK REM	EACH	3,352.000				