

# SCHEDULE OF QUANTITIES

44200974	CLASS B PATCHES, TYPE III, 10"			
SQ YD	LOCATION	OFFSET	REMARKS	
	LASALLE CO TO MCGIRR RD			
21	REST AREA		1@ 12'	
44200976	CLASS B PATCHES, TYPE IV, 10"			
SQ YD	LOCATION	OFFSET	REMARKS	
	LASALLE CO TO MCGIRR RD			
	REST AREA			
348	RAMP A		1@ 21' & 1@ 175'	
27	RAMP B		1@ 15'	
139	RAMP C		1@ 22' & 1@ 30' WITH SHOULDER	
514	TOTAL			

48100100	AGGREGATE SHOULDERS, TYPE A			
TON	LOCATION	OFFSET	REMARKS	
	MCGIRR RD TO OGLE CO			
	STEWARD CREEK			
32	1177+30 TO 1178+39		SB LT	
40	1177+30 TO 1178+39		SB MEDIAN	
159	1181+20 TO 1185+50		NB MEDIAN	
161	1183+00 TO 1187+35		SB MEDIAN	
	BNSF RR			
62	1189+23 TO 1190+90		NB MEDIAN	
47	1191+65 TO 1192+91		SB MEDIAN	
	PERRY ROAD			
37	1195+13 TO 1196+13		NB MEDIAN	
37	1195+13 TO 1196+13		NB RT	
575	TOTAL			

44213000	PATCHING REINFORCEMENT			
SQ YD	LOCATION	OFFSET	REMARKS	
	LASALLE CO TO MCGIRR RD			
7090	TO BE USED AS DIRECTED BY RE/TE			
	MCGIRR RD TO OGLE CO			
2360	TO BE USED AS DIRECTED BY RE/TE			
9450	TOTAL			

44213200	SAW CUTS			
FOOT	LOCATION	OFFSET	REMARKS	
	LASALLE CO TO MCGIRR RD			
23373	TO BE USED AS DIRECTED BY RE/TE		CLASS A PATCHES	
1100	CHICAGO ROAD		CLASS B PATCHES	
1132	REST AREA		CLASS B PATCHES	
954	US 30		CLASS B PATCHES	
26559	SUBTOTAL			
	MCGIRR RD TO OGLE CO			
7791	TO BE USED AS DIRECTED BY RE/TE		CLASS A PATCHES	
1190	PERRY ROAD		CLASS B PATCHES	
8981	SUBTOTAL			
35540	TOTAL			

**REVISED**  
 **5-27-10**  
 SHEET

FILE NAME =	USER NAME = stringer.jn	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b>	<b>I-39</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\pwwork\STRINGER.JN\d0149531\205809-shr-schedule.dgn		DRAWN -	REVISED -	<b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	39	(103-1, 103-2)RS	LEE	313	62
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
PLOT DATE = Tue May 25 07:29:07 2010		DATE -	REVISED -							
										ILLINOIS FED. AID PROJECT CONTRACT NO. 64E97