

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	LASALLE TO MCGIRR 100% State 1000	MCGIRR TO OGLE 100% State 1000	Bridge Repair 100% State FTY-2A
52100520	ANCHOR BOLTS, 1"	EACH	196			196
59000200	EPOXY CRACK INJECTION	FOOT	12			12
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	36	12	24	
60107600	PIPE UNDERDRAINS 4"	FOOT	8167	2912	5255	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	640	180	460	
60260100	INLETS TO BE ADJUSTED	EACH	6	6		
60262405	INLETS TO BE ADJUSTED WITH NEW MEDIAN INLET (604101)	EACH	10	7	3	
60600605	CONCRETE CURB, TYPE B	FOOT	1936		1936	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	3837.5	600.0	3237.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	22	4	18	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	10	4	6	
63200310	GUARDRAIL REMOVAL	FOOT	4717	956	3761	
63300575	REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	650	250	400	

*** SPECIALTY ITEMS**

FILE NAME =	USER NAME = dossed	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 SUMMARY OF QUANTITIES	F.A.I RTE. 39	SECTION (103-1, 103-2)RS	COUNTY LEE	TOTAL SHEETS 313	SHEET NO. 12	
or\pw\work\pw\dot\dossed\0149531\020589	9-ah-t-S00.dgn	DRAWN -	REVISED -								
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -								
	PLOT DATE = Mon Mar 29 13:27:56 2010	DATE -	REVISED -								
						SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
						ILLINOIS FED. AID PROJECT CONTRACT NO. 64E97					