

PAVEMENT SCHEDULE MAINLINE

LOCATION	REMARKS	MAINLINE		40600200		40600300		40600400		40600855		40600985		40603245		40603575		44000198		X0322729		
				BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)		MIX FOR CRACKS JOINTS & FLANGEWAYS		POLY HMA LEVEL BINDER (MM) N105		PCC SURFACE REMOVAL BUTT JOINT		POLY HMA BINDER COURSE IL-19.0, N105		POLY HMA SURFACE COURSE MIX "E" N105		HMA SURFACE REMOVAL VAR DEPTH		MATERIAL TRANSFER DEVICE		
				TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	
		FT	SQ YD	SQ YD	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE
North Bound																						
McGirr Road to Ogle County																						
1087 + 62 - 1177 + 76	160' Taper & Removal at Wide Flange Beam	9014	12018	12018	10.37	10.37	54.40	54.40	12.80	12.80	841	841	67	67	1514	1514	1098	1098	213	213	3454	3454
1177 + 76 - 1196 + 13	See Structure Plans	1837	2449	2449																	0	0
1196 + 13 - 1198 + 32	Perry Rd - Ramp G Opening 160' Taper & Rem at W Flange Beam	219	292	292	0.31	0.31	1.63	1.63	0.31	0.31	20	20	67	67	37	37	51	51	213	213	109	109
1198 + 32 - 1201 + 95	Perry Rd - Ramp G Gore	363	484	484	0.42	0.42	2.18	2.18	0.52	0.52	34	34			61	61	43	43			138	138
1201 + 95 - 1214 + 17	Perry Rd Between Ramps	1221	1629	1629	1.40	1.40	7.33	7.33	1.73	1.73	114	114			205	205	145	145			465	465
1214 + 17 - 1216 + 18	Perry Rd - Ramp H Gore	202	269	269	0.23	0.23	1.21	1.21	0.29	0.29	19	19			34	34	24	24			77	77
1216 + 18 - 1226 + 0	Perry Rd - Ramp H Opening	982	1309	1309	1.12	1.12	5.89	5.89	1.39	1.39	92	92			165	165	117	117			373	373
1226 + 0 - 1351 + 86		12566	16755	16755	14.38	14.38	75.40	75.40	17.85	17.85	1173	1173			2111	2111	1495	1495			4779	4779
1351 + 66 - 1353 + 86	Tie into Ogle Co 5" Overlay	220	293	293	0.25	0.25	1.32	1.32	0.31	0.31	21	21			37	37	26	26	293	293	84	84
McGirr Road to Ogle County		SUBTOTAL			28.5	28.5	149.4	149.4	35.2	35.2	2313	2313	133	133	4164	4164	3000	3000	720	720	9478	9478
					57.0		298.8		70.4		4626		266		8328		6000		1440		18956	

South Bound																						
LaSalle County to McGirr Road																						
320 + 50 - 321 + 0	LaSalle County - Butt Joint	50	67	67									67	67								
320 + 50 - 322 + 50	LaSalle County - 40:1 Taper	200	267	267	0.23	0.23	1.20	1.20	0.28	0.28	19	19			34	34	24	24			76	76
322 + 50 - 338 + 84	LaSalle County	1634	2179	2179	1.87	1.87	9.80	9.80	2.32	2.32	152	152			274	274	194	194			621	621
338 + 84 - 495 + 41		15657	20876	20876	17.91	17.91	93.94	93.94	22.24	22.24	1461	1461			2630	2630	1863	1863			5955	5955
495 + 41 - 499 + 31	Shady Oaks - Profile Adjustment	390	520	520	0.45	0.45	2.34	2.34	0.55	0.55	36	36			66	66	46	46			148	148
499 + 31 - 601 + 85		10254	13672	13672	11.73	11.73	61.52	61.52	14.57	14.57	957	957			1723	1723	1220	1220			3900	3900
601 + 85 - 608 + 48	Chicago Rd - Ramp A Opening	663	884	884	0.76	0.76	3.98	3.98	0.94	0.94	62	62			111	111	79	79			252	252
608 + 48 - 612 + 68	Chicago Rd - Ramp A Gore	420	560	560	0.48	0.48	2.52	2.52	0.60	0.60	39	39			71	71	50	50			160	160
612 + 68 - 638 + 65		2597	3463	3463	2.97	2.97	15.58	15.58	3.69	3.69	242	242			436	436	309	309			988	988
638 + 65 - 642 + 36	Chicago Rd - Ramp D Gore	371	495	495	0.42	0.42	2.23	2.23	0.53	0.53	35	35			62	62	44	44			141	141
642 + 36 - 645 + 25	Chicago Rd - Ramp D Opening	289	385	385	0.33	0.33	1.73	1.73	0.41	0.41	27	27			49	49	34	34			110	110
645 + 25 - 719 + 38		7414	9885	9885	8.48	8.48	44.48	44.48	10.53	10.53	692	692			1245	1245	882	882			2820	2820
719 + 38 - 741 + 26	Rest Area - Ramp A Opening	2188	2917	2917	2.50	2.50	13.13	13.13	3.11	3.11	204	204			368	368	260	260			832	832
741 + 26 - 744 + 88	Rest Area - Ramp A Gore	362	482	482	0.41	0.41	2.17	2.17	0.51	0.51	34	34			61	61	43	43			138	138
744 + 88 - 771 + 15		2627	3502	3502	3.01	3.01	15.76	15.76	3.73	3.73	245	245			441	441	313	313			999	999
771 + 15 - 775 + 9	Rest Area - Ramp D Gore	394	525	525	0.45	0.45	2.36	2.36	0.56	0.56	37	37			66	66	47	47			150	150
775 + 9 - 777 + 77	Rest Area - Ramp D Opening	268	357	357	0.31	0.31	1.61	1.61	0.38	0.38	25	25			45	45	32	32			102	102
775 + 9 - 852 + 97		7788	10384	10384	8.91	8.91	46.73	46.73	11.06	11.06	727	727			1308	1308	927	927			2962	2962
852 + 97 - 862 + 43	US 30 - Ramp A Opening	946	1262	1262	1.08	1.08	5.68	5.68	1.34	1.34	88	88			159	159	113	113			360	360
862 + 43 - 865 + 4	US 30 - Ramp A Gore	261	348	348	0.30	0.30	1.57	1.57	0.37	0.37	24	24			44	44	31	31			99	99