

PAVEMENT SCHEDULE MAINLINE

LOCATION	REMARKS	40600200		40600300		40600400		40600855		40600985		40603245		40603575		44000198		X0322729				
		LENGTH	MAINLINE		BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)		MIX FOR CRACKS JOINTS & FLANGEWAYS		POLY HMA LEVEL BINDER (MM) N105		PCC SURFACE REMOVAL BUTT JOINT		POLY HMA BINDER COURSE IL-19.0, N105		POLY HMA SURFACE COURSE MIX "E" N105		HMA SURFACE REMOVAL VAR DEPTH		MATERIAL TRANSFER DEVICE	
			FT	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON
South Bound			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE		
865 + 4 - 874 + 87	160' Taper & Removal at Wide Flange Beam	983	1311	1311	1.19	1.19	6.22	6.22	1.40	1.40	92	92	67	67	165	165	142	142	213	213	399	399
874 + 87 - 879 + 30	US 30 See Structure Plans	443	591	591																		
879 + 30 - 889 + 38	160' Taper & Removal at Wide Flange Beam	1008	1345	1345	1.21	1.21	6.37	6.37	1.43	1.43	94	94	67	67	169	169	145	145	213	213	409	409
889 + 38 - 891 + 73	US 30 - Ramp D Gore	235	313	313	0.27	0.27	1.41	1.41	0.33	0.33	22	22			39	39	28	28			89	89
891 + 73 - 901 + 33	US 30 - Ramp D Opening	960	1280	1280	1.10	1.10	5.76	5.76	1.36	1.36	90	90			161	161	114	114			365	365
901 + 33 - 1086 + 13		18480	24640	24640	21.14	21.14	110.88	110.88	26.25	26.25	1725	1725			3105	3105	2199	2199			7029	7029
LaSalle County to McGirr Road			SUBTOTAL		87.5	87.5	459.0	459.0	108.5	108.5	7130	7130	200	200	12833	12833	9141	9141	427	427	29104	29104
					175.0		918.0		217.0		14260		400		25666		18282		854		58208	

South Bound																						
McGirr Road to Ogle County																						
1086 + 13 - 1089 + 23	Mc Girr - Profile Adjustment	310	413	413	0.35	0.35	1.86	1.86	0.44	0.44	29	29			52	52	37	37			118	118
1089 + 23 - 1177 + 31	160' Taper & Removal at Wide Flange Beam	8808	11744	11744	10.14	10.14	53.17	53.17	12.51	12.51	822	822	67	67	1480	1480	1074	1074	213	213	3375	3375
1177 + 31 - 1196 + 13	See Structure Plans	1882	2509	2509																	0	0
1196 + 13 - 1199 + 12	Perry Rd - Ramp F Gore 160' Taper & Removal at W Flange Beam	299	399	399	0.40	0.40	2.12	2.12	0.43	0.43	28	28	67	67	50	50	61	61	213	213	139	139
1199 + 12 - 1210 + 90	Perry Rd Between Ramps	1178	1571	1571	1.35	1.35	7.07	7.07	1.67	1.67	110	110			198	198	140	140			448	448
1210 + 90 - 1214 + 63	Perry Rd - Ramp E Gore	373	497	497	0.43	0.43	2.24	2.24	0.53	0.53	35	35			63	63	44	44			142	142
1214 + 63 - 1217 + 88	Perry Rd - Ramp E Opening	324	432	432	0.37	0.37	1.95	1.95	0.46	0.46	30	30			54	54	39	39			123	123
1217 + 88 - 1351 + 66		13379	17838	17838	15.31	15.31	80.27	80.27	19.00	19.00	1249	1249			2248	2248	1592	1592			5088	5088
1351 + 66 - 1353 + 86	Tie into Ogle Co 5" Overlay	220	293	293	0.25	0.25	1.32	1.32	0.31	0.31	21	21			37	37	26	26	293	293	84	84
McGirr Road to Ogle County			SUBTOTAL		28.6	28.6	150.0	150.0	35.4	35.4	2323	2323	133	133	4182	4182	3013	3013	720	720	9518	9518
					57.2		300.0		70.8		4646		266		8364		6026		1440		19036	

LaSalle County to McGirr Road			TOTAL		174.9	174.9	917.3	917.3	216.8	216.8	14240	14240	400	400	25626	25626	18269	18269	854	854	58134	58134
					349.8		1834.6		433.6		28480		800		51252		36538		1708		116268	
McGirr Road to Ogle County			TOTAL		57.1	57.1	299.4	299.4	70.6	70.6	4636	4636	266	266	8346	8346	6013	6013	1440	1440	18996	18996
					114.2		598.8		141.2		9272		532		16692		12026		2880		37992	
GRANDTOTAL					464		2433.4		574.8		37752		1332		67944		48564		4588		154260	