

PAVEMENT SCHEDULE SHOULDERS

LOCATION	REMARKS	LENGTH FT	SHOULDERS		SHOULDERS		BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)		HMA SURFACE COURSE MIX "C" N50		AGGREGATE SHOULDERS, TYPE A		HMA SHOULDERS SPECIAL		REM AND REINSTALL DELINEATORS	SHOULDER RUMBLE STRIPS		MATERIAL TRANSFER DEVICE
			WIDTH		AREA		TON		TON		TON		TON		TON		EACH	FOOT		TON
			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	OUTSIDE	INSIDE	OUTSIDE	OUTSIDE
South Bound																				
LaSalle County to McGirr Road Cont.																				
862 + 43 - 865 + 4	US 30 - Ramp & Gore	261.2	6	Var	174	286	0.15		0.78		15		34		27		1	261		
865 + 4 - 874 + 87		982.9	6	10	655	1092	0.56	0.94	2.95	4.91	55	92	126	72	103	141	2	983	983	232
874 + 87 - 879 + 30	US 30 See Structure Plans	443	6	10	295	492											1			
879 + 30 - 889 + 38		1008.4	6	10	672	1120	0.58	0.96	3.03	5.04	56	94	130	74	105	144	3	1008	1008	238
889 + 38 - 891 + 73	US 30 - Ramp Gore	234.6	6	Var	156	472	0.13		0.70		13		30		25		1	235		
891 + 73 - 901 + 33	US 30 - Ramp Opening	959.3	6	6 & Var	640	216	0.55		2.88		54		124		100		2	960		
901 + 33 - 1086 + 13		18480.2	6	10	12320	20534	10.57	17.62	55.44	92.40	1035	1725	2378	1347	1932	2645	46	18480	18480	4370
SUBTOTAL							43.7	65.6	229.2	344.2	4278	6426	9831	5018	7985	9853	192	76388	68847	16278
							109.3		573.4		10704		14849		17838			145235		

McGirr Road to Ogle County																				
1086 + 13 - 1089 + 23	Mc Girr - Profile Adjustment	310	6	10	207	344	0.18	0.30	0.93	1.55	17	29	40	23	32	44	1	310	310	73
1089 + 23 - 1177 + 31		8808	6	10	5872	9787	5.04	8.40	26.42	44.04	493	822	1134	642	921	1261	22	8808	8808	2083
1177 + 31 - 1196 + 13	See Structure Plans	1882	6	10	1255	2091											5			
1196 + 13 - 1199 + 12	Perry Rd - Ramp Gore	299.3	6	Var	200	180	0.17		0.90		17		39		31		1	299		
1199 + 12 - 1210 + 90	Perry Rd Between Ramps	1177.9	6	8	785	1047	0.67	0.90	3.53	4.71	86	88	152	86	123	135	3	1178	1178	223
1210 + 90 - 1214 + 63	Perry Rd - Ramp Gore	373	6	Var	249	413	0.21		1.12		21		48		39		1	373		
1214 + 63 - 1217 + 88	Perry Rd - Ramp Opening	324.3	6	6 & Var	216	242	0.19		0.97		18		42		34		1	324		
1217 + 88 - 1351 + 66		13378.5	6	10	8919	14865	7.65	12.75	40.14	66.89	749	1249	1722	975	1398	1915	33	13379	13379	3163
1351 + 66 - 1353 + 86	Tie into Ogle Co 5" Overlay	220	6	10	147	244	0.13	0.21	0.66	1.10	12	21	28	16	23	31	1	220	220	52
SUBTOTAL							14.2	22.6	74.7	118.3	1394	2208	3203	1742	2602	3386	67	24891	23894	5594
							36.8		193.0		3602		4945		5988			48785		

LaSalle County to McGirr Road	TOTAL	88.2	132.6	462.3	695.4	8670	12981	19717	10137	16127	20034	384	152665	139082	33304
		220.8		1157.7		21651		29854		36162			291747		

McGirr Road to Ogle County	TOTAL	28.6	44.3	150.3	232.2	2817	4334	6413	3420	5241	6646	134	49678	46915	11062
		72.9		382.5		7151		9833		11887			96593		

GRANDTOTAL	293.7	1540.2	28802	39687	48049	518	388340	44366
-------------------	-------	--------	-------	-------	-------	-----	--------	-------