

# PAVEMENT MARKING SCHEDULE MAINLINE

LOCATION	REMARKS	LENGTH FT	70300100			70300220		70300240		70300250		70300260			70301000			78008300		78008310		78008330		78008340		78008350		
			SHORT-TERM PAVEMENT MARKING			TEMPORARY PAVT MARKING - LINE 4"		TEMPORARY PAVT MARKING - LINE 6"		TEMPORARY PAVT MARKING - LINE 8"		TEMPORARY PAVT MARKING - LINE 12"		WORK ZONE PAVEMENT MARKING REMOVAL			POLYUREA PAVT MARKING TY II LETTERS & SYMBOLS		POLYUREA PAVT MARKING TY II - LINE 4"		POLYUREA PAVT MARKING TY II - LINE 6"		POLYUREA PAVT MARKING TY II - LINE 8"		POLYUREA PAVT MARKING TY II - LINE 12"			
			INSIDE	CENTER	OUTSIDE	INSIDE	OUTSIDE	CENTERLINE	GORE	DIAGONALS	INSIDE	CENTER	OUTSIDE	SQ FT			SQ FT		FOOT		FOOT		FOOT		FOOT			
<b>South Bound</b>																												
<b>LaSalle County to McGirr Road</b>						YELLOW	WHITE	WHITE	WHITE	WHITE								YELLOW	WHITE	WHITE	WHITE	WHITE						
862 + 43 - 865 + 4	US 30 - Ramp A Gore	261	31	31		522		131	1045				185	76	697					261		65	522					
865 + 4 - 874 + 87	160' Taper & Removal at Wide Flange Beam	983	118	118	118	1966	1966	491					695	285	695					983	983	246						
874 + 87 - 879 + 30	US 30 See Structure Plans	443	53	53	53	886	886	222					313	128	313					443	443	111						
879 + 30 - 889 + 38	160' Taper & Removal at Wide Flange Beam	1008	121	121	121	2017	2017	504					713	292	713					1008	1008	252						
889 + 38 - 891 + 73	US 30 - Ramp D Gore	235	28	28		469		117	938	240			166	68	866					235		59	469	130				
891 + 73 - 901 + 33	US 30 - Ramp D Opening	960	115	115		1920		480					678	278						960		240						
901 + 33 - 1086 + 13		18480	2218	2218	2218	36960	36960	9240					13059	5359	13059					18480	18480	4620						
AERIAL SPEED CHECK CONTACT STATE POLICE FOR LOCATION																		40.5										
<b>LaSalle County to McGirr Road</b>			9220	9220	8315	153662	138579	38416	8170	720	54294	22281	55131				40.5	76831	69290	19208	4085	390						
			26755			292241						131706					146121											

<b>McGirr Road to Ogle County</b>																														
LOCATION	REMARKS	LENGTH	INSIDE	CENTER	OUTSIDE	INSIDE	OUTSIDE	CENTERLINE	GORE	DIAGONALS	INSIDE	CENTER	OUTSIDE	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
1086 + 13 - 1089 + 23	Mc Girr - Profile Adjustment	310	37	37	37	620	620	155					219	90	219					310	310	78								
1089 + 23 - 1177 + 31	160' Taper & Removal at Wide Flange Beam	8808	1057	1057	1057	17616	17616	4404					6224	2554	6224					8808	8808	2202								
1177 + 31 - 1196 + 13	See Structure Plans	1882	226	226	226	3764	3764	941					1330	546	1330					1882	1882	471								
1196 + 13 - 1199 + 12	Perry Rd - Ramp E Gore 160' Taper & Removal at W Flange Beam	299	36	36		599		150	1197				212	87	798					299		75	599							
1199 + 12 - 1210 + 90	Perry Rd Between Ramps	1178	141	141	141	2356	2356	589					832	342	832					1178	1178	294								
1210 + 90 - 1214 + 63	Perry Rd - Ramp E Gore	373	45	45		746		187	1492	240			264	108	1235					373		93	746	120						
1214 + 63 - 1217 + 88	Perry Rd - Ramp E Opening	324	39	39		649		162					229	94						324		81								
1217 + 88 - 1351 + 86		13379	1605	1605	1605	26757	26757	6689					9454	3880	9454					13379	13379	3345								
1351 + 86 - 1353 + 86	Tie into Ogle Co 5" Overlay	220	26	26	26	440	440	110					155	64	155					220	220	55								
<b>McGirr Road to Ogle County</b>			3213	3213	3093	53546	51553	13387	2689	240	18920	7764	20248		0	26773	25776	6693	1345	120										
			9519			105099						46932			52549															

<b>LaSalle County to McGirr Road</b>			18425	18425	16795	307086	279919	76772	16922	1440	108504	44528	111626		81	153543	139960	38386	8461	750										
			53645			587006						264658			293503															

<b>McGirr Road to Ogle County</b>			6408	6408	6076	106794	101269	26699	4949	480	37734	15485	39561		0	53397	50635	13349	2475	240										
			18892			208063						92780			104032															

<b>GRAND TOTAL</b>	72537	795069	103471	21871	1920	357438	81	397535	51735	10936	990
--------------------	-------	--------	--------	-------	------	--------	----	--------	-------	-------	-----

NOTE: SHORT-TERM AND TEMPORARY PAVEMENT MARKING ASSUMES 2 APPLICATIONS

FILE NAME =	USER NAME = dossed	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-39 PAVEMENT MARKING SCHEDULE</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pw\work\pwi\dot\dossed\0149531\0225899-sh-rpm.dgn	DRAWN -	REVISED -	39			(103-1, 103-2)RS	LEE	313	42	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 64E97							
PLOT DATE = Mon Mar 29 11:25:15 2010	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT