

SCHEDULE OF QUANTITIES

20800150 TRENCH BACKFILL

CUYD	LOCATION	OFFSET	REMARKS
	<u>MCGIRR RD TO OGLE CO</u>		
5	1177+35 TO 1178+39	SB LT	104
5	1177+35 TO 1178+39	SB MEDIAN	104
5	1177+80 TO 1178+84	NB MEDIAN	104
5	1177+80 TO 1178+84	NB RT	104
22	1180+75 TO 1185+50	SB LT	475
21	1180+87 TO 1185+50	SB MEDIAN	463
20	1181+20 TO 1185+50	NB MEDIAN	430
19	1181+35 TO 1185+50	NB RT	415
9	1185+50 TO 1187+35	SB LT	185
9	1185+50 TO 1187+35	SB MEDIAN	185
7	1185+50 TO 1187+01	NB MEDIAN	151
7	1185+50 TO 1187+01	NB RT	151
15	1189+57 TO 1192+86	SB LT	329
15	1189+57 TO 1192+86	SB MEDIAN	329
17	1189+23 TO 1192+86	NB MEDIAN	363
17	1189+23 TO 1192+86	NB RT	363
4	1195+13 TO 1196+08	SB LT	95
4	1195+13 TO 1196+08	SB MEDIAN	95
4	1195+13 TO 1196+08	NB MEDIAN	95
4	1195+13 TO 1196+08	NB RT	95
214	TOTAL		

PIPE UNDERDRAIN
TRENCH AREA (2 FT *8") = 1.3333
DEDUCT PIPE AREA - 4"dia = 0.0873
NET AREA = 1.2460

UNIT	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
1	360+40 TO 361+40	LT	
2	728+86 TO 730+86	RT	
2	916+09 TO 918+09	RT	
3	988+50	RT	CHANNEL - FLOWLINE 300'
8	CHICAGO RD		4 GORE AREAS EST. 200' EA
8	REST AREA		4 GORE AREAS EST. 200' EA
8	US 30		4 GORE AREAS EST. 200' EA
14	INLET ADJUST		EST. 100' ON EA SIDE OF INLET
25	AS DIRECTED BY RE/TE		
71	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
8	PERRY RD		4 GORE AREAS EST. 200' EA
11	PERRY RD		BETWEEN RAMP G & H
4	INLET ADJUST		EST. 100' ON EA SIDE OF INLET
25	AS DIRECTED BY RE/TE		
48	SUBTOTAL		
119	TOTAL		

20200100 EARTH EXCAVATION

CUYD	LOCATION	OFFSET	REMARKS
	<u>LASALLE CO TO MCGIRR RD</u>		
2254	SHADY OAKS		
2589	BEEMERVILLE		
1476	US 30		THIS LOCATION WILL REQUIRE 100 CY FOR GUARDRIAL
6319	SUBTOTAL		
	<u>MCGIRR RD TO OGLE CO</u>		
904	MCGIRR		
8734	STRUCTURES		
9638	SUBTOTAL		
15957	TOTAL		

25000210 SEEDING CLASS 2A

ACRE	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
0.26	SHADY OAKS		
0.36	BEEMERVILLE		
0.44	US 30		
4.07	GRADING AND SHAPING DITCHES		
5.13	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
0.01	MCGIRR		
1.30	STRUCTURES		
2.75	GRADING AND SHAPING DITCHES		
4.06	SUBTOTAL		
9.2	TOTAL		