

SCHEDULE OF QUANTITIES

28100107 STONE RIPRAP, CLASS A4			
SQ YD	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
91	360+23	LT	8' PERIMETER AROUND DROP BOX
22	729+86	RT	20' X 10'
39	917+09	RT	TRAPEZOID 25' X 45' X 10'
39	988+50	RT	TRAPEZOID 25' X 45' X 10'
39	1029+75	RT	TRAPEZOID 25' X 45' X 10'
230	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
13	1266+75	RT	TRAPEZOID 10' X 24' X 7'
243	TOTAL		

31100910 SUB-BASE GRANULAR MATERIAL, TYPE A, 12"			
SQ YD	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
US 30			
456	874+87 TO 875+87	SB	LANES
456	874+91 TO 875+91	NB	LANES
456	878+26 TO 879+26	NB	LANES
456	878+29 TO 879+29	SB	LANES
1824	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
STEWARD CREEK			
497	1177+30 TO 1178+39	SB	LANES
497	1177+76 TO 1178+85	NB	LANES
3030	1180+78 TO 1187+35	SB	LANES
2663	1181+24 TO 1187+01	NB	LANES
BNSF RR			
1696	1189+23 TO 1192+91	NB	LANES
1710	1189+57 TO 1192+91	SB	LANES
PERRY ROAD			
492	1195+13 TO 1196+13	NB	LANES
610	1195+13 TO 1196+13	SB	LANES
11195	SUBTOTAL		
13019	TOTAL		

28200200 FILTER FABRIC			
SQ YD	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
91	360+23	LT	UNDER RIPRAP
22	729+86	RT	UNDER RIPRAP
39	917+09	RT	UNDER RIPRAP
39	988+50	RT	UNDER RIPRAP
39	1029+75	RT	UNDER RIPRAP
230	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
13	1266+75	RT	UNDER RIPRAP
243	TOTAL		

31100300 SUB-BASE GRANULAR MATERIAL TYPE A, 4"			
SQ YD	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
2918	USE AT LOCATIONS OF CLASS A PATCHES, TYPE IV, 10"		
<u>MCGIRR RD TO OGLE CO</u>			
972	USE AT LOCATIONS OF CLASS A PATCHES, TYPE IV, 10"		
3890	TOTAL		