

SCHEDULE OF QUANTITIES

60108100 PIPE UNDERDRAINS, 4" (SPECIAL)

FOOT	LOCATION	OFFSET	REMARKS
	<u>MCGIRR RD TO OGLE CO</u>		
	Steward Creek		
20	1177+35	SB LT	
20	1177+35	SB MEDIAN	
20	1177+80	NB MEDIAN	
20	1177+80	NB RT	
20	1180+75	SB LT	
20	1180+87	SB MEDIAN	
20	1181+20	NB MEDIAN	
20	1181+35	NB RT	
20	1185+50	NB RT	
20	1185+50	NB MEDIAN	
20	1185+50	SB LT	
20	1185+50	SB MEDIAN	
	<u>BNRR</u>		
20	1192+86	SB LT	
20	1192+86	SB MEDIAN	
20	1192+86	NB MEDIAN	
20	1192+86	NB RT	
	<u>Perry Rd</u>		
20	1196+08	SB LT	
20	1196+08	SB MEDIAN	
20	1196+08	NB MEDIAN	
20	1196+08	NB RT	
400	TOTAL		

60262405 INLETS TO BE ADJUSTED WITH NEW MEDIAN INLET (604101)

EACH	LOCATION	OFFSET	REMARKS
	<u>LASALLE CO TO MCGIRR RD</u>		
4	TO BE USED AS DIRECTED BY RE/TE		
1	347+13		
1	360+23		
1	689+92		
7	SUBTOTAL		
	<u>MCGIRR RD TO OGLE CO</u>		
3	TO BE USED AS DIRECTED BY RE/TE		
3	SUBTOTAL		
10	TOTAL		

60600605 CONCRETE CURB, TYPE B

FOOT	LOCATION	OFFSET	REMARKS
	<u>MCGIRR RD TO OGLE CO</u>		
	Steward Creek		
657	1180+78 TO 1187+35	SB LT	
578	1181+24 TO 1187+01	NB RT	
	<u>Perry Rd</u>		
368	1189+23 TO 1192+91	NB RT	
334	1189+57 TO 1192+91	SB LT	
1936	TOTAL		

60260100 INLETS TO BE ADJUSTED

EACH	LOCATION	OFFSET	REMARKS	
	<u>LASALLE CO TO MCGIRR RD</u>			
	CHICAGO ROAD			
1	638+60	SB LT	INCLUDES CLEANING AND 2' PERIMETER REPLACEMENT FOR ALL INLETS TO BE ADJUSTED	
1	639+28	NB RT		
	<u>US 30</u>			
1	862+88	NB RT		
1	863+55	SB LT		
1	891+27	SB LT		
1	891+29	NB RT		
6	SUBTOTAL			