

SCHEDULE OF QUANTITIES

63300575 REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARDRAIL

FOOT	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
US 30			
50	875+81 TO 876+21	NB MEDIAN	
50	877+99 TO 878+49	SB MEDIAN	
150	877+99 TO 878+49	SB LT	
250	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
STEWARD CREEK			
150	1177+63 TO 1179+13	NB RT	
50	1178+47 TO 1178+97	NB MEDIAN	
PERRY ROAD			
150	1194+70 TO 1196+20	SB LT	
50	1194+84 TO 1195+34	SB MEDIAN	
400	SUBTOTAL		
650	TOTAL		

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
SB LANES STAGE 1			
1465	869+80 TO 884+45	SB MEDIAN	4" YELLOW
2370	869+80 TO 893+50	SB LT	4" WHITE
230	891+20 TO 893+50	GORE	4" WHITE
2130	891+20 TO 912+50	SB LT	4" WHITE
NB LANES STAGE 1			
2070	842+00 TO 862+70	NB RT	4" WHITE
170	861+00 TO 862+70	GORE	4" WHITE
2341	861+00 TO 884+41	NB RT	4" WHITE
1466	869+75 TO 884+41	NB MEDIAN	4" YELLOW
SB LANES STAGE 2			
1575	869+15 TO 884+90	SB LT	4" WHITE
3075	869+15 TO 899+90	SB MEDIAN	4" YELLOW
400	891+20 TO 895+20	GORE	4" WHITE
400	891+20 TO 895+20	GORE	4" WHITE
120	891+20 TO 895+20	GORE	DIAGNALS
NB LANES STAGE 2			
4306	842+00 TO 885+06	NB MEDIAN	4" YELLOW
350	859+30 TO 862+80	GORE	4" WHITE
350	859+30 TO 862+80	GORE	4" WHITE
120	859+30 TO 862+80	GORE	DIAGNALS
1575	869+31 TO 885+06	NB RT	4" WHITE
24513	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
SB LANES STAGE 1			
2900	1172+10 TO 1201+10	SB MEDIAN	4" YELLOW
4090	1172+10 TO 1213+00	SB LT	4" WHITE
200	1211+00 TO 1213+00	GORE	4" WHITE
2100	1211+00 TO 1232+00	SB LT	4" WHITE
NB LANES STAGE 1			
4485	1157+15 TO 1202+00	NB RT	4" WHITE
2830	1172+80 TO 1201+10	NB MEDIAN	4" YELLOW
75	1201+25 TO 1202+00	GORE	4" WHITE

66502405 WOVEN WIRE FENCE REMOVAL AND REPLACEMENT

FOOT	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
251	916+10 TO 917+95		FOR GRADING AND SHAPING DITCHES
210	987+45 TO 989+40		AND RIPRAP PLACEMENT
461	TOTAL		

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
2	US 30 STRUCTURE		CONTACT SURVEY DEPARTMENT
<u>MCGIRR RD TO OGLE CO</u>			
3	STEWARD CREEK, BNSF RR, & PERRY ROAD		
5	TOTAL		