

# SCHEDULE OF QUANTITIES

70300220 TEMPORARY PAVEMENT MARKING - LINE 4" CONT.

70301000 WORK ZONE PAVEMENT MARKING REMOVAL - CONT.

| FOOT                        | LOCATION           | OFFSET    | REMARKS   |
|-----------------------------|--------------------|-----------|-----------|
| <u>MCGIRR RD TO OGLE CO</u> |                    |           |           |
| SB LANES STAGE 2            |                    |           |           |
| 3280                        | 1171+45 TO 1204+25 | SB LT     | 4" WHITE  |
| 4780                        | 1171+45 TO 1219+25 | SB MEDIAN | 4" YELLOW |
| 360                         | 1211+00 TO 1214+60 | GORE      | 4" WHITE  |
| 360                         | 1211+00 TO 1214+60 | GORE      | 4" WHITE  |
| 120                         | 1211+00 TO 1214+60 | GORE      | DIAGNALS  |
| NB LANES STAGE 2            |                    |           |           |
| 4460                        | 1157+15 TO 1201+75 | NB MEDIAN | 4" YELLOW |
| 2980                        | 1172+15 TO 1201+95 | NB RT     | 4" WHITE  |
| 275                         | 1199+00 TO 1201+75 | GORE      | 4" WHITE  |
| 120                         | 1199+00 TO 1201+75 | GORE      | 4" WHITE  |
| 33415                       | SUBTOTAL           |           |           |
| 57928                       | TOTAL              |           |           |

| SQ FT   | LOCATION           | OFFSET    | REMARKS   |
|---|--------------------|-----------|-----------|
| <u>MCGIRR RD TO OGLE CO</u>                     |                    |           |           |
| SB LANES STAGE 2 (REM PAV MK PLACED IN STAGE 1) |                    |           |           |
| 120   | 1172+10 TO 1175+71 | SB MEDIAN | 4" YELLOW |
| 120   | 1172+10 TO 1175+71 | SB LT     | 4" WHITE  |
| 112   | 1197+73 TO 1201+10 | SB MEDIAN | 4" YELLOW |
| 509   | 1197+73 TO 1213+00 | SB LT     | 4" WHITE  |
| 67  | 1211+00 TO 1213+00 | GORE      | 4" WHITE  |
| 700   | 1211+00 TO 1232+00 | SB LT     | 4" WHITE  |
| NB LANES STAGE 2 (REM PAV MK PLACED IN STAGE 1) |                    |           |           |
| 634   | 1157+15 TO 1176+16 | NB RT     | 4" WHITE  |
| 112   | 1172+80 TO 1176+16 | NB MEDIAN | 4" YELLOW |
| 142   | 1197+73 TO 1202+00 | NB RT     | 4" WHITE  |
| 112   | 1197+73 TO 1201+10 | NB MEDIAN | 4" YELLOW |
| 25  | 1201+25 TO 1202+00 | GORE      | 4" WHITE  |
| SB LANES (REM PAV MK PLACED IN STAGE 2)         |                    |           |           |
| 1093  | 1171+45 TO 1204+25 | SB LT     | 4" WHITE  |
| 1593  | 1171+45 TO 1219+25 | SB MEDIAN | 4" YELLOW |
| SB LANES (REM PAV MK PLACED IN STAGE 2)         |                    |           |           |
| 1487  | 1157+15 TO 1201+75 | NB MEDIAN | 4" YELLOW |
| 993   | 1172+15 TO 1201+95 | NB RT     | 4" WHITE  |
| 92  | 1199+00 TO 1201+75 | GORE      | 4" WHITE  |
| 92  | 1199+00 TO 1201+75 | GORE      | 4" WHITE  |
| 8004  | SUBTOTAL           |           |           |
| 14583   | TOTAL              |           |           |

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

| SQ FT   | LOCATION         | OFFSET    | REMARKS   |
|---|------------------|-----------|-----------|
| <u>LASALLE CO TO MCGIRR RD</u>                  |                  |           |           |
| SB LANES STAGE 2 (REM PAV MK PLACED IN STAGE 1) |                  |           |           |
| 116   | 869+80 TO 873+27 | SB MEDIAN | 4" YELLOW |
| 116   | 869+80 TO 873+27 | SB LT     | 4" WHITE  |
| 118   | 880+90 TO 884+45 | SB MEDIAN | 4" YELLOW |
| 420   | 880+90 TO 893+50 | SB LT     | 4" WHITE  |
| 77  | 891+20 TO 893+50 | GORE      | 4" WHITE  |
| 710   | 891+20 TO 912+50 | SB LT     | 4" WHITE  |
| NB LANES STAGE 2 (REM PAV MK PLACE IN STAGE 1)  |                  |           |           |
| 690   | 842+00 TO 862+70 | NB RT     | 4" WHITE  |
| 57  | 861+00 TO 862+70 | GORE      | 4" WHITE  |
| 410   | 861+00 TO 873+31 | NB RT     | 4" WHITE  |
| 119   | 869+75 TO 873+31 | NB MEDIAN | 4" YELLOW |
| 118   | 880+86 TO 884+41 | NB RT     | 4" WHITE  |
| 118   | 880+86 TO 884+41 | NB MEDIAN | 4" YELLOW |
| SB LANES (REM PAV MK PLACED IN STAGE 2)         |                  |           |           |
| 525   | 869+15 TO 884+90 | SB LT     | 4" WHITE  |
| 1025  | 869+15 TO 899+90 | SB MEDIAN | 4" YELLOW |
| NSB LANES (REM PAV MK PLACED IN STAGE 2)        |                  |           |           |
| 1435  | 842+00 TO 885+06 | NB MEDIAN | 4" YELLOW |
| 525   | 869+31 TO 885+06 | NB RT     | 4" WHITE  |
| 6579  | SUBTOTAL         |           |           |

70400100 TEMPORARY CONCRETE BARRIER

| FOOT                           | LOCATION           | OFFSET   | REMARKS |
|--------------------------------|--------------------|----------|---------|
| <u>LASALLE CO TO MCGIRR RD</u> |                    |          |         |
| 1025                           | 872+90 TO 883+15   | SB LANES |         |
| 1025                           | 871+06 TO 881+31   | NB LANES |         |
| 2050                           | SUBTOTAL           |          |         |
| <u>MCGIRR RD TO OGLE CO</u>    |                    |          |         |
| 2475                           | 1175+20 TO 1199+95 | SB LANES |         |
| 2400                           | 1173+90 TO 1197+90 | NB LANES |         |
| 4875                           | SUBTOTAL           |          |         |
| 6925                           | TOTAL              |          |         |