

# SCHEDULE OF QUANTITIES

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
1025	872+90 TO 883+15	SB LANES	
1025	871+06 TO 881+31	NB LANES	
2050	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
2475	1175+20 TO 1199+95	SB LANES	
2400	1173+90 TO 1197+90	NB LANES	
4875	SUBTOTAL		
6925	TOTAL		

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
US 30			
8	876+17 TO 877+99	SB LT & MEDIAN	
8	876+21 TO 877+96	NB RT & MEDIAN	
16	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
STEWARD CREEK			
8	1178+77 TO 1180+37	SB LT & MEDIAN	
8	1179+29 TO 1181+02	NB RT & MEDIAN	
BNSF RR			
8	1187+74 TO 1189+35	SB LT & MEDIAN	
8	1187+20 TO 1188+86	NB RT & MEDIAN	
PERRY ROAD			
8	1193+15 TO 1194+91	SB LT & MEDIAN	
8	1193+15 TO 1194+91	NB RT & MEDIAN	
48	SUBTOTAL		
64	TOTAL		

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	OFFSET	REMARKS
<u>LASALLE CO TO MCGIRR RD</u>			
US 30			
4	873+52 TO 876+21	NB RT	CRYSTAL
4	874+05 TO 876+20	NB MEDIAN	AMBER
4	877+99 TO 880+18	SB MEDIAN	AMBER
4	877+99 TO 880+68	SB LT	CRYSTAL
16	SUBTOTAL		
<u>MCGIRR RD TO OGLE CO</u>			
STEWARD CREEK			
4	1176+44 TO 1179+13	NB RT	CRYSTAL
4	1176+78 TO 1178+97	NB MEDIAN	AMBER
10	1180+66 TO 1187+62	SB LT	CRYSTAL
4	1180+66 TO 1182+85	SB MEDIAN	AMBER
9	1181+13 TO 1187+15	NB RT	CRYSTAL
BNSF RR			
4	1185+07 TO 1187+26	NB MEDIAN	AMBER
6	1189+45 TO 1193+21	NB RT	CRYSTAL
6	1189+33 TO 1193+21	NB MEDIAN	AMBER
6	1189+10 TO 1193+21	SB MEDIAN	AMBER
6	1189+02 TO 1193+21	SB LT	CRYSTAL
PERRY ROAD			
4	1194+84 TO 1197+03	SB MEDIAN	AMBER
4	1194+83 TO 1197+52	SB LT	CRYSTAL
66	SUBTOTAL		
82	TOTAL		