



BILL OF MATERIAL

Bar	No.	Size	Length	Shape
d10(E)	9	#5	24'-3"	—
a11(E)	9	#5	19'-11"	—
q12(E)	6	#6	4'-0"	—
b3(E)	40	#5	2'-3"	┘
d(E)	5	#4	4'-10"	┘
d1(E)	5	#5	3'-11"	┘
h(E)	4	#6	24'-3"	—
h1(E)	4	#6	19'-11"	—
Reinforcement Bars, Epoxy Coated			Pound	850
Concrete Removal			Cu. Yd.	6.7
Concrete Superstructure			Cu. Yd.	7.6
Bar Splicers			Each	13
Protective Coat			Sq. Yd.	3

Quantity for Top & Inside Face of Reconstructed Parapets

SECTION A-A

SECTION A'-A'

**PROPOSED PLAN
NORTH ABUTMENT AT
SOUTHBOUND STRUCTURE**

LEGEND:
O.F. = Outside Face
I.F. = Inside Face

* Remove portion of Wingwall as required at corners to allow clearance for new deck overhang.
Cut Reinforcement Bars flush and seal surface with epoxy. Cost included with Concrete Removal.