

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Summary of Quantities							URBAN Y035
PAY CODE	ITEM	UNIT	SITE 404	SITE 405	SITE 406	SITE 407	TOTAL (100% STATE)
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD		35.5	35.5		71
* 63000002	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6.75 FOOT POSTS	FOOT		62.5			62.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH		1			1
67100100	MOBILIZATION	L SUM	0.25	0.25	0.25	0.25	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	0.25	0.25	0.25	0.25	1
73301600	OVERHEAD SIGN STRUCTURE - BUTTERFLY, TYPE I-B-A	FOOT	15.75	15.75	15.75	15.75	63
73301900	OVERHEAD SIGN STRUCTURE WALKWAY - BUTTERFLY, TYPE A	FOOT	15.75	15.75	15.75	15.75	63
73400100	CONCRETE FOUNDATIONS	CU YD		11.5	11.5	11.5	34.5
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7				7
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	1	1	4
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	200	165	140	50	555
81018525	CONDUIT PUSHED, 2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	60	65			125
81400100	HANDHOLE	EACH	2	2			4
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	180	180	420	300	1,080
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	600	495	90	105	1,290
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	250	205	175	65	695
87800500	CONCRETE FOUNDATION (SPECIAL)	FOOT	5.5	5.5	5.5	5.5	22
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	1	1	1		3
⚠ X0325871	INSTALL DYNAMIC MESSAGE SIGN	EACH	1	1	1	1	4
X0326812	CAT 5 ETHERNET CABLE	FOOT	60	60	140	50	310

* SPECIALTY ITEM

⚠ REVISED 5-26-10

DESIGNED - S. POSKA	2010
CHECKED - G. STUEMPFIG	EXAMINED
DRAWN - M. BRESSLER	ENGINEER OF BRIDGE DESIGN
CHECKED - G. STUEMPFIG	PASSED
	ENGINEER OF BRIDGES AND STRUCTURES



George M. Stuempfig
3/8/10

SHEET NO. 2	F.A. RTE. 74+280	SECTION D2.IT MESSAGE SIGN	COUNTY ROCK ISLAND	TOTAL SHEETS 23	SHEET NO. 2
CONTRACT NO. 64F86					
ILLINOIS FED. AID PROJECT C-92-061-10					