

PATCHING SCHEDULE - IL 17			
LOCATION WBL LOG MILE	CLASS B TYPE II	DOWEL BARS	SAW CUTS
	SQ YD	EACH	FOOT
0.00	BEGIN CONCRETE SECTION		
0.05	8	20	48
0.08	8	20	48
0.10	8	20	48
0.11	8	20	48
0.12	13	20	56
0.13	8	20	48
0.14	8	20	48
0.14	8	20	48
0.15	11	20	52
0.20	8	20	48
0.20	13	20	56
0.21	8	20	48
0.21	13	20	56
0.35	8	20	48
0.40	8	20	48
0.40	8	20	48
0.42	8	20	48
0.44	8	20	48
0.55	8	20	48
0.60	8	20	48
0.65	END CONCRETE SECTION		
WB TOTALS	179	400	988

PATCHING SCHEDULE - IL 17			
LOCATION EBL LOG MILE	CLASS B TYPE II	DOWEL BARS	SAW CUTS
	SQ YD	EACH	FOOT
0.65	BEGIN CONCRETE SECTION		
0.55	8	20	48
0.50	8	20	48
0.48	8	20	48
0.45	8	20	48
0.35	13	20	56
0.36	8	20	48
0.30	8	20	48
0.29	8	20	48
0.25	11	20	52
0.21	8	20	48
0.15	13	20	56
0.08	8	20	12
0.00	END CONCRETE SECTION		
EB TOTALS	109	240	596