

PATCHING SCHEDULE - SBL

LOCATION BY MILE MARKER	PASSING LANE					DRIVING LANE					REMARKS
	CLASS A PATCHING TYPE II SQ YD	CLASS A PATCHING TYPE IV SQ YD	PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	CLASS A PATCHING TYPE II SQ YD	CLASS A PATCHING TYPE IV SQ YD	PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	
57.42											US RTE. 6
56.80						13	0	13	78		
55.37											IL RTE. 351
54.46											OGLESBY SPUR
54.20						8	0	8	66		
53.13											IL RTE. 251
52.85						8		8	66		
52.80						13		13	78		
52.40	8		8	60							
52.37											IL RTE. 71
52.20						13		13	78		
51.30						8		8	66		
50.50						8		8	66		
50.40						8		8	66		
48.70						8		8	66		
48.50											RAY RICHARDSON ROAD
48.20	8		8	60							
48.10	8		8	60							
47.70						11		11	72		
47.30						8		8	66		
44.70	8		8	60							
43.70						11		11	72		
42.30						13		13	78		
42.20						8		8	66		
41.40											IL RTE. 18
40.70	8		8	60							
40.24											MARSHALL COUNTY LINE
SUBTOTALS	40	0	40	300	0	139	0	139	984		
TOTALS	40	0	80	600	0	437	25	463	3172		

FILE NAME = c:\p\work\PWIDOT\WOODSHANKRL\02143168

USER NAME = woodshankr1  
 0366A31-detail1.dgn  
 PLOT SCALE = 100.0000' / IN.  
 PLOT DATE = Mar 31, 2010 - 08:19:45 AM

DESIGNED - RON WOODSHANK  
 DRAWN - RON WOODSHANK  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULES - SBL

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D3 PATCHING 2011-2	LASALLE	16	8
CONTRACT NO. 66A31			ILLINOIS	