

SUMMARY OF QUANTITIES					H24	LS3E	H24	LS3E		
SPL	CODE NO.	PAYITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	I000	I000	Y031-1F	Y031-1F	Y031-1F	Y030-1E
					ROADWAY	ROADWAY	SIGNALS	SIGNALS	SIGNALS	LIGHTING
					80/20	90/10	80/13.3/6.7	90/10	90/10	90/10
							IL 29 & LASALLE	IL 29 & WESLEY		IL 29 & WESLEY
		MARQ HTS	N. PEKIN	DET LOOPS						
	40600990	TEMPORARY RAMP	SQ YD	340	340					
	40603565	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	1485	1485					
	42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SQ YD	155		155				
	44000100	PAVEMENT REMOVAL	SQ YD	866		866				
	44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	647	647					
	44000198	HOT - MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	18637	18637					
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	279		279				
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	628		628				
	44002805	ISLAND REMOVAL	SQ FT	513		513				
	44003100	MEDIAN REMOVAL	SQ FT	6321		6321				
	44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1290		1290				
	44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	516	516					
	44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	211	211					
	44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	59	59					
	44213100	PAVEMENT FABRIC	SQ YD	270	270					
	44213200	SAW CUTS	FOOT	4422	4422					
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	32	32					
	48203025	HOT - MIX ASPHALT SHOULDERS, 7"	SQ YD	301		301				
	48203100	HOT - MIX ASPHALT SHOULDERS	TON	316	316					
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	3		3				
	60240330	INLETS, TYPE B, TYPE 37 GRATE	EACH	1		1				
	60262700	INLETS TO BE RECONSTRUCTED	EACH	2		2				

FILE NAME = Summary of Quantities.dgn

USER NAME = lobebsidm	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/25/2010	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 669	SECTION (11)RS-9L-2,N,TS-4	COUNTY TAZEWELL	TOTAL SHEETS 102	SHEET NO. 7
CONTRACT NO. 68590			[ILLINOIS] FED. AID PROJECT	