

SUMMARY OF QUANTITIES					H24	LS3E	H24	LS3E		
SPL	CODE NO.	PAYITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	I000	I000	Y031-1F	Y031-1F	Y031-1F	Y030-1E
					ROADWAY	ROADWAY	SIGNALS	SIGNALS	SIGNALS	LIGHTING
					80/20	90/10	80/13.3/6.7	90/10	90/10	90/10
							IL 29 & LASALLE MARQ HTS	IL 29 & WESLEY N. PEKIN		IL 29 & WESLEY
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5.5		5.5				
	60603500	COMB. CONC. CURB AND GUTTER, TYPE B-6.06	FOOT	573		573				
	60603800	COMB. CONC. CURB AND GUTTER, TYPE B-6.12	FOOT	568		568				
	60605000	COMB. CONC. CURB AND GUTTER, TYPE B-6.24	FOOT	1009		1009				
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2600		2600				
	60622800	CONCRETE MEDIAN, TYPE SM-6.12	SQ FT	79		79				
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10		10				
	67100100	MOBILIZATION	L SUM	1	1					
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1			0.3	0.7		
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	21		21				
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12696		12696				
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	465		465				
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7256		7256				
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1070		1070				
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2695		2695				
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	533		533				
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	263		263				
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6593		6593				
X	72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	6			3	3		

X SPECIALTY ITEM

FILE NAME = Summary of Quantities .dgn	USER NAME = jlabodism	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 669	SECTION (1)RS-9,L-2,N,TS-4	COUNTY TAZEWELL	TOTAL SHEETS 102	SHEET NO. 8
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 68590		
	PLOT DATE = 3/25/2010	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -										