

SUMMARY OF QUANTITIES					H24	LS3E	H24	LS3E		
QTY	CODE NO.	PAYITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	I000	I000	Y031-1F	Y031-1F	Y031-1F	Y030-1E
					ROADWAY	ROADWAY	SIGNALS	SIGNALS	SIGNALS	LIGHTING
					80/20	90/10	80/13.3/6.7	90/10	90/10	90/10
							IL 29 & LASALLE	IL 29 & WESLEY		IL 29 & WESLEY
						MARQ HTS	N. PEKIN	DET LOOPS		
X	87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	3274			1068.5	2205.5		
X	87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	2				2		
X	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1		
X	87700420	STEEL MAST ARM ASSEMBLY AND POLE, 70 FT.	EACH	2				2		
X	87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1				1		
X	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6				6		
X	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5				3.5		
X	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26				26		
X	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	50				50		
X	87900200	DRILL EXISTING HANDHOLE	EACH	3			2	1		
X	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6				6		
X	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3				3		
X	88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	3			2	1		
X	88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	2				2		
X	88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	10			2	8		
X	88500100	INDUCTIVE LOOP DETECTOR	EACH	21			10	11		
X	88600100	DETECTOR LOOP, TYPE I	FOOT	1871					1871	
X	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1				1		
X	89502215	MODIFY EXISTING CONTROLLER FOUNDATION	EACH	1			1			
X	89502380	REMOVE EXISTING HANDHOLE	EACH	10				10		
X	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6				6		
	X0322729	MATERIAL TRANSFER DEVICE	TON	1156	1156					

X SPECIALTY ITEM

FILE NAME = Summary of Quantities .dgn	USER NAME = l06b0d1sm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 669	SECTION (1)RS-9,L-2,N,TS-4	COUNTY TAZEWELL	TOTAL SHEETS 102	SHEET NO. 10		
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 68590				
PLOT DATE = 3/25/2018	DATE -	REVISED -	REVISED -									