

| TABULATION OF PCC QUANTITIES | | | | |
|-------------------------------|-------------------------|--|---|---------------------------|
| LOCATION | PCC BASE CSE, 12 1/4 IN | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION (INCLUDES MEDIAN & CURBED AREAS) | SUB-BASE GRANULAR MATRL, TY A 12 IN (INCLUDES MEDIAN & CURBED AREAS) | PCC DRIVEWAY PAV'T, 10 IN |
| | SQYD | SQYD | SQYD | SQYD |
| IL 29 | | | | |
| Sta 242+89 - Sta 21+21 ** | 12.22 | 67.78 | 67.78 | |
| Sta 242+97.5 - Sta 243+21.29 | 22.56 | 22.56 | 22.56 | |
| Sta 243+71.24 - Sta 243+96.41 | 20.78 | 20.78 | 20.78 | |
| Sta 244+30.5 - Sta 244+46.96 | 13.33 | 13.33 | 13.33 | |
| Sta 244+31.77 Sta 247+20.52 | 203.33 | 203.33 | 203.33 | |
| Sta 243+17 - Sta 4+86 * | 333.33 | 771.11 | 771.11 | |
| WESLEY RD | | | | |
| Sta 16+96.72 - Sta 16+26 | 187.22 | 279.44 | 279.44 | 37.77 |
| Sta 16+96.72 - Sta 18+94 | 161.11 | 211.67 | 211.67 | 73.67 |
| MAIN ST | | | | |
| Sta 21+24 - Sta 22+38 | 30.00 | 30.00 | 30.00 | 42.89 |
| * Sta Equation 246+17 = 0+00 | | | | |
| ** Use Wesley Rd Stationing | | | | |
| | SUBTOTAL | 983.9 | 1620.00 | 154.33 |
| | TOTAL | 985 | 1620 | 155 |

| TABULATION ON RIPRAP | | |
|-------------------------|---------------------|---------------|
| LOCATION | STONE RIPRAP, CL A4 | FILTER FABRIC |
| | SQYD | SQYD |
| IL 29 | | |
| Sta 244+89 - Sta 245+73 | 86.55 | 86.55 |
| WESLEY RD | | |
| Sta 17+46 - Sta 17+60 | 12.64 | 12.64 |
| | SUBTOTAL | 99.19 |
| | TOTAL | 100.0 |

| TABULATION OF RAISED REFLECTIVE PAVEMENT MARKER | | | |
|---|-----------------------------------|---------------|---|
| LOCATION | RAISED REFLECTIVE PAVEMENT MARKER | | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL |
| | EACH | EACH | EACH |
| | 1 - WAY CRYSTAL | 2 - WAY AMBER | |
| IL 29 - Mainline | | | |
| Northbound | | | |
| Sta 247+80 - Sta 8+50 * | 35 | 9 | 35 |
| Southbound | | | |
| Sta 247+80 - Sta 8+50 * | 50 | 9 | 50 |
| * Sta Equation 242+17 = 0+00 | | | |
| | SUBTOTAL | 85 | 18 |
| | TOTAL | 103 | 85 |