

TABULATION OF EARTHWORK QUANTITIES						
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (FOR INFO ONLY) 25%	EMBANKMENT (FOR INFO ONLY)	EARTHWORK BALANCE SURPLUS (+) & SHORTAGE (-) (FOR INFO ONLY)	TOPSOIL FURNISH & PLACE 4"	GRADING & SHAPING DITCHES
	CUYD	CUYD	CUYD	CUYD	SQYD	FOOT
WESLEY RD - NW QUAD	67.7	50.8	236.8	-186.0	999.0	
WESLEY RD - NE QUAD	113.1	84.8	16.0	68.8	2353.0	
MAIN ST - SW QUAD	47.7	35.8	7.4	28.4	614.0	130.0
MAIN ST - SE QUAD	1.4	1.1	0.3	0.8	74.0	
IL 29 - MEDIAN REMOVAL AREA	324.8	243.6	0.0	243.6		
SUB-TOTAL	554.7	416.0	260.5	155.5	4040.0	130.0
TOTAL	555	416	260	+ 156	4040	130

TABULATION OF TEMPORARY EROSION CONTROL QUANTITIES					
LOCATION	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL SEEDING (1 APP. EVERY 7 DAYS)	INLET & PIPE PROTECTION	MULCH, METHOD 1 (3 APPLICATIONS)
	FOOT	FOOT	POUND	EACH	ACRE
WESLEY RD - NW QUAD	-	245.0	225	-	0.63
WESLEY RD - NE QUAD	242.0	852.0	525	1	1.47
MAIN ST - SW QUAD	53.5	-	140	-	0.39
MAIN ST - SE QUAD	-	185.0	21	1	0.06
SUB-TOTAL	295.50	1282.00	911.00	2	2.55
TOTAL	296	1282	911	2	2.6

TABULATION OF PERMANENT EROSION CONTROL QUANTITIES (SEEDING)					
LOCATION	NITROGEN FERT NUTRIENT	PHOSPHORUS FERT NUTRIENT	POTASSIUM FERT NUTRIENT	SEEDING CL 2A	EROSION CONTROL BLANKET
	POUND	POUND	POUND	ACRES	SQYD
WESLEY RD - NW QUAD	18.9	18.9	18.9	0.21	999.0
WESLEY RD - NE QUAD	44.1	44.1	44.1	0.49	2353.0
MAIN ST - SW QUAD	11.7	11.7	11.7	0.13	614.0
MAIN ST - SE QUAD	1.8	1.8	1.8	0.02	74.0
SUBTOTAL	76.5	76.5	76.5	0.85	4040
TOTAL	77	77	77	0.85	4040

FILE NAME = Schedules of Quantities.dgn

USER NAME = jlabbe@idm

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 1/8" = 1' / IN.

CHECKED -

REVISED -

PLOT DATE = 3/25/2018

DATE -

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	(11)RS-9,L-2,N,TS-4	TAZEWELL	122	22
CONTRACT NO. 68590				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				