

SUMMARY OF QUANTITIES

S P L I T T Y	CODE	ITEM DESCRIPTION	UNIT	TOTAL QTY.	CONST. TYPE CODE MERCER COUNTY Y007 100% STATE
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	30
	20100500	TREE REMOVAL, ACRES	ACRE	0.1	0.1
	20200100	EARTH EXCAVATION	CU YD	528	528
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	76	76
	20400800	FURNISHED EXCAVATION	CU YD	1256	1256
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	23	23
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	155	155
	21101615	TOPSOIL FURNISH ^{AND} PLACE, 4"	SQ YD	1785	1785
	25000300	SEEDING, CLASS 3	ACRE	0.3	0.3
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27
	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1785	1785
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30	30
	28000400	PERIMETER EROSION BARRIER	FOOT	105	105
	28100207	STONE RIPRAP, CLASS A 4	TON	252	252
	50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2
	50300225	CONCRETE STRUCTURES	CU YD	0.5	0.5
	50800105	REINFORCEMENT BARS	POUND	70	70
	54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1
	54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1	1
	54002020	EXPANSION BOLTS 3/4 INCH	EACH	12	12
	54010505	PRECAST CONCRETE BOX CULVERT 5' X 5'	FOOT	39	39
	54010404	PRECAST CONCRETE BOX CULVERT 4' X 4'	FOOT	47	47
	54248510	CONCRETE COLLAR	CU YD	3.1	3.1
	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
	67100100	MOBILIZATION	L SUM	1	1
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
	Z0054500	ROCK FILL	TON	127	127
	X0325758	MANHOLES, TYPE A, 8' DIAMETER, TYPE B GRATE	EACH	1	1
	X0323986	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	720	720



REVISED
5-28-2010

FILE NAME =
D468704-sht-plan.dgn

USER NAME = longer
DESIGNED -
DRAWN -
PLOT SCALE = 40,0000' / IN.
CHECKED -
PLOT DATE = 4/8/2010
DATE -

REVISIONS
 REVISION
 REVISION
 REVISION
 REVISION

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
639	D4 CULVERT REPAIR	MERCER	33	3
CONTRACT NO. 68929			ILLINOIS FED. AID PROJECT	