

SEEDING, CLASS 3	
LOCATION	ACRE
LOCATION #1	0.2
LOCATION #2	0.1
TOTAL	0.3

TOPSOIL FURNISH & PLACE 4"	
LOCATION	SQ. YD.
LOCATION #1	1135.0
LOCATION #2	650.0
TOTAL	1785.0

LOCATION	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS
	EACH
LOCATION #1	
STA 1078+25 OFFSET 50' RT	1
STA 1079+25 OFFSET 120' RT	1
STA 1079+75 OFFSET 120' RT	1
STA 1080+75 OFFSET 50' RT	1
LOCATION #2	
STA 1093+50 OFFSET 42.40' RT	1
STA 1094+00 OFFSET 90' RT	1
STA 1095+00 OFFSET 90' RT	1
STA 1095+50 OFFSET 40' RT	1
TOTALS	8

TEMPORARY EROSION CONTROL SEEDING	
LOCATION	POUND
LOCATION #1	20.0
LOCATION #2	10.0
TOTAL	30.0

PERIMETER EROSION BARRIER	
LOCATION	FOOT
LOCATION #1	75.0
LOCATION #2	30.0
TOTAL	105.0

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL, ACRES
	UNIT	ACRE
LOCATION #1	30	
LOCATION #2		0.1
TOTALS	30	0.1

NITROGEN FERTILIZER NUTRIENT	
LOCATION	POUND
LOCATION #1	18.0
LOCATION #2	9.0
TOTAL	27.0

STONE RIPRAP, CLASS A4	
LOCATION	TON
LOCATION #1	211.0
LOCATION #2	41.0
TOTAL	252.0

PHOSPHORUS FERTILIZER NUTRIENT	
LOCATION	POUND
LOCATION #1	18.0
LOCATION #2	9.0
TOTAL	27.0

EARTH EXCAVATION	
LOCATION	CU YD
LOCATION #1	495
LOCATION #2	33
TOTAL	528

POTASSIUM FERTILIZER NUTRIENT	
LOCATION	POUND
LOCATION #1	18.0
LOCATION #2	9.0
TOTAL	27.0

FURNISHED EXCAVATION			
LOCATION	CUT*	FILL	CY
LOCATION #1	371.3	815.3	444.1
LOCATION #2	24.7	836.8	812.1
TOTAL			1256

HEAVY DUTY EROSION CONTROL BLANKET	
LOCATION	SQ. YD.
LOCATION #1	1135.0
LOCATION #2	650.0
TOTAL	1785.0

\* EARTH EXCAVATION WITH 25% SHRINKAGE


  
**SHEET**  
**REVISED**  
**5-28-2010**

FILE NAME =  
D468784-sht-plan.dgn

USER NAME = horstkj	DESIGNED -	REVISED -
PLOT SCALE = 48.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 5/27/2010	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
639	D4 CULVERT REPAIR	MERCER	33	7
CONTRACT NO. 68929				
ILLINOIS FED. AID PROJECT				