

## SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	I000 PEORIA COUNTY 100% STATE	I000 KNOX COUNTY 100% STATE	I000 VILLAGE 50/50 ELMWOOD	I000 VILLAGE 100 ELMWOOD
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	22	21	1		
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL*4.75, <span style="margin-left: 150px;">N50 →</span>	TON	1,235	1,175	60		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT*MIX ASPHALT SURFACE REMOVAL * BUTT JOINT	SQ YD	2,561	2,534	27		
40600990	TEMPORARY RAMP	SQ YD	561	548	13		
40603560	POLYMERIZED HOT*MIX ASPHALT SURFACE COURSE, MIX "E", <span style="margin-left: 150px;">N50 →</span>	TON	2,469	2,354	115		
40800050	INCIDENTAL HOT*MIX ASPHALT SURFACING	TON	525	525			
44000157	HOT*MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	40,155	29,120	1,890	8670	475
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	290	290			
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	60	60			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	413	355	58		
48203100	HOT*MIX ASPHALT SHOULDERS	TON	1,170	20		1095	55
6700040	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			
67100100	MOBILIZATION	L SUM	1	0.9	0.1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.9	0.1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.9	0.1		
70300100	SHORT*TERM PAVEMENT MARKING	FOOT	5,438	5,183	255		
70300220	TEMPORARY PAVEMENT MARKING * LINE 4"	FOOT	31,275	29,711	1,564		
70300240	TEMPORARY PAVEMENT MARKING * LINE 6"	FOOT	320	320			
70300250	TEMPORARY PAVEMENT MARKING * LINE 8"	FOOT	640	640			
70300280	TEMPORARY PAVEMENT MARKING * LINE 24"	FOOT	48	48			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	363	346	17		
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	138	131	7		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	138	131	7		

(X) SPECIALTY  
ITEM

FILE NAME =  
68958 Phase II.dgn

USER NAME = jacobsmr  
PLOT SCALE = 100.0000' / IN.  
PLOT DATE = 3/18/2018

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	46RS-3;131RS-5	KNOX/PEORIA	18	4
ILLINOIS				
CONTRACT NO. 68958				