

LOCATION			LENGTH	AREA	HMA SURF REMOVAL (2")	POLY LEVEL BIND(MM) IL-4.75, N50 (3/4")	HMA SURF CSE MIX "D" N50 (1 1/2")	POLY BIT MAT (PR CT)
			FT	SQ.YD	SQ.YD	TON	TON	TON
KNOX COUNTY								
1505+00	TO	1510+10	510	1,360.00	1,360.00	57.12	114.24	0.71
PEORIA COUNTY								
1510+10	TO	1519+65	955	2,546.67	2,546.67	106.96	213.92	1.32
100+00	TO	103+22	322	858.67	858.67	36.06	72.13	0.45
103+22	TO	139+90	3,668	16,300.00	16,300.00	410.82	821.63	8.48
139+90	TO	144+09	419	2,610.20	2,610.20	46.93	93.86	1.36
1226+80	TO	1232+04	524	1,397.30	1,397.30	58.69	117.38	0.73
0+00	TO	29+28	2,928	7,808.00	7,808.00	327.94	655.87	4.06
29+28	TO	30+85	157	558.20	558.20	34.58	68.17	0.29
30+85	TO	41+90	1,105	4,930.10	4,930.10	123.76	247.52	2.55
41+90	TO	44+77	287	1,785.80	1,785.80	32.14	64.29	0.93
KNOX COUNTY				1,360.00	1,360.00	57.12	114.24	0.71
PEORIA COUNTY				38,775.94	38,775.94	1,177.88	2,354.76	20.16
GRAND TOTALS				40,155	40,155	1,235	2,469	21

LOCATION	WIDTH	HOT-MIX ASPHALT SURF REMOVAL-BUTT JOINT	TEMP RAMP	INCIDENTAL HMA SURF
	FT	SQ YD	SQ YD	TON
KNOX COUNTY				
STARTING STA. 1505+05	24.00	26.70	13.33	0.00
PEORIA COUNTY				
MOUND ST	22.00	76.30	12.22	9.56
KNOX ST	80.00	249.30	44.44	50.38
LOCUST ST	80.00	250.50	44.44	50.34
ELM ST	48.00	166.70	26.67	36.86
WALNUT ST	48.00	169.80	26.67	36.40
MORGAN ST	36.00	137.90	20.00	31.66
ALTHEA ST	48.00	167.80	26.67	36.67
LILAC ST	72.00	177.20	40.00	41.47
MAGNOLIA ST	56.00	72.30	31.11	23.49
MAIN ST	56.00	76.70	31.11	19.33
EVERGREEN ST	104.00	243.10	57.78	47.82
CYPRESS ST	48.00	165.60	26.67	36.54
BUTTERNUT ST	48.00	166.70	26.67	39.45
ASH ST	48.00	164.10	26.67	36.88
ENTRANCE RT STA. 7+95	50.00	49.80	27.78	14.75
ENTRANCE LT STA. 6+99	54.00	61.70	30.00	5.92
SOUTH GATE D DRIVE STA. 4+60	88.00	138.90	48.89	7.30
ENDING STA. 1226+80	24.00	26.70	13.33	0.00
KNOX COUNTY		26.70	13.33	0.00
PEORIA COUNTY		2,534.40	547.78	521.82
Total		2,561	561	525

RATES:

FOR ALL HOT MIXES: 112 lbs/Sq.Yd.in.
 FOR AGGREGATE SHOULDERS TYPE B: 2.05 ton/cu.yd
 FOR BIT MATLS (PRIME COAT): 0.004 ton/gal
 -ON GRANULAR BASE: 0.5 GAL/SQ. YD.
 -ON EXIST. PVT.: 0.05 GAL/SQ.YD.
 -ON COLD MILLED AREA: 0.1 GAL/SQ.YD.
 -ON NEW PAV'T: 0.03 GAL/SQ.YD.

RESURFACING TABLE SUMMARY

PAY ITEM	HMA SURF REMOVAL 2"	HMA SURF REMOVAL BUTT JOINTS	HMA SURF CSE MIX "D" N50 1 1/2"	POLY LEVEL BIND (MM) IL-4.75 N50 (3/4")	INCIDENTAL HMA SURFACE	HMA SHOULDERS (RT & LT)
UNIT	SQ YD	SQ YD	TON	TON	TON	TON
	40,136	2,588	2,469	1,235	522	1,162
TOTAL	42,724 SQYD			5,388 TONS		

* NOTE SEE EACH TABLE FOR BREAK DOWN QUANTITY