

| HMA SHOULDERS | | | | | | | |
|---------------|--------|----|--------|-------|------------------------------|----------------------|--------|
| LOCATION | | | LENGTH | AREA | HMA SHOULDER (RT,LT) REMOVAL | HMA SHOULDER (RT,LT) | |
| | | | FT | SQ.YD | SQ YD | TON | |
| PEORIA COUNTY | | | | | | | |
| LT | 103+22 | TO | 103+87 | 65 | 28.90 | 28.90 | 3.64 |
| LT | 103+87 | TO | 117+00 | 1,313 | 1,167.11 | 1,167.11 | 147.06 |
| LT | 117+85 | TO | 120+39 | 254 | 225.77 | 225.77 | 28.45 |
| LT | 121+24 | TO | 123+75 | 251 | 223.11 | 223.11 | 28.11 |
| LT | 124+44 | TO | 127+10 | 266 | 236.44 | 236.44 | 29.79 |
| LT | 127+79 | TO | 130+26 | 247 | 219.55 | 219.55 | 27.66 |
| LT | 130+89 | TO | 136+10 | 521 | 463.11 | 463.11 | 58.35 |
| LT | 136+80 | TO | 139+98 | 310 | 275.55 | 275.55 | 34.72 |
| LT | 140+53 | TO | 143+97 | 344 | 611.55 | 611.55 | 77.06 |
| RT | 104+00 | TO | 117+00 | 1,300 | 1,155.55 | 1,155.55 | 145.60 |
| RT | 117+85 | TO | 120+39 | 254 | 225.77 | 225.77 | 28.45 |
| RT | 121+24 | TO | 123+75 | 251 | 223.11 | 223.11 | 28.11 |
| RT | 124+44 | TO | 127+10 | 266 | 236.44 | 236.44 | 29.79 |
| RT | 127+79 | TO | 130+26 | 247 | 219.55 | 219.55 | 27.66 |
| RT | 130+89 | TO | 136+10 | 521 | 463.11 | 463.11 | 58.35 |
| RT | 136+80 | TO | 139+90 | 310 | 275.55 | 275.55 | 34.72 |
| RT | 140+53 | TO | 143+76 | 323 | 574.20 | 574.20 | 72.35 |
| LT | 42+47 | TO | 44+44 | 197 | 350.22 | 350.22 | 44.13 |
| LT | 39+68 | TO | 41+67 | 199 | 176.88 | 176.88 | 22.29 |
| LT | 35+90 | TO | 39+00 | 310 | 275.55 | 275.55 | 42.72 |
| LT | 32+00 | TO | 35+21 | 321 | 285.33 | 285.33 | 35.95 |
| LT | 30+85 | TO | 31+32 | 47 | 41.77 | 41.77 | 5.26 |
| LT | 29+28 | TO | 30+85 | 157 | 69.80 | 69.80 | 8.79 |
| RT | 42+47 | TO | 44+44 | 197 | 350.20 | 350.20 | 44.13 |
| RT | 39+69 | TO | 41+68 | 199 | 176.88 | 176.88 | 22.29 |
| RT | 35+90 | TO | 39+00 | 310 | 275.55 | 275.55 | 34.72 |
| RT | 32+00 | TO | 35+21 | 321 | 285.33 | 285.33 | 35.95 |
| RT | 30+85 | TO | 31+32 | 47 | 41.77 | 41.77 | 5.26 |
| RT | 29+28 | TO | 30+85 | 157 | 69.80 | 69.80 | 8.79 |
| GRAND TOTALS | | | | | 9,223 | 9,223 | 1,170 |

| LOCATION | LENGTH | AREA | AGG SHOULDER TYPE B (RT,LT) |
|--------------------|--------|----------|-----------------------------|
| | FT | SQ.YD | TON |
| KNOX COUNTY | | | |
| 1505+00 TO 1510+10 | 510 | 226.70 | 58.08 |
| PEORIA COUNTY | | | |
| 1510+10 TO 1519+65 | 955 | 424.40 | 108.8 |
| 100+00 TO 103+50 | 350 | 155.00 | 39.9 |
| 0+00 TO 12+90 | 1,290 | 573.30 | 146.9 |
| 1226+80 TO 1232+04 | 524 | 232.90 | 59.7 |
| KNOX COUNTY | | 226.70 | 58.08 |
| PEORIA COUNTY | | 1,385.60 | 355.3 |
| GRAND TOTALS | | 1,612.3 | 413.38 |

| RAISED REFLECTIVE PAVEMENT MARKING | | | | | |
|------------------------------------|-------|-------|--------|-----------------------------|------------------------------|
| LOCATION | | | LENGTH | RAISED REF PAVEMENT MARKERS | RAISED REF PVT MRKRS REMOVAL |
| | | | FT | EACH | EACH |
| KNOX COUNTY | | | | | |
| 1505+00 TO 1510+10 | 510 | 7.00 | 5.00 | | |
| PEORIA COUNTY | | | | | |
| 1510+10 TO 1519+65 | 955 | 12.00 | 10.00 | | |
| 100+00 TO 144+09 | 4,409 | 56.00 | 56.00 | | |
| 1226+80 TO 1232+04 | 524 | 7.00 | 5.00 | | |
| 0+00 TO 44+77 | 4,477 | 56.00 | 54.00 | | |
| KNOX COUNTY | | | 510 | 7.00 | 5.00 |
| PEORIA COUNTY | | | 10,365 | 131.00 | 125.00 |
| TOTAL | | | 10,875 | 138 | 130 |

| CLASS D PATCHING SCHEDULE (13 INCH) | | |
|---|---------------|----------------|
| LOCATION | PEORIA COUNTY | |
| | TYPE II SQ YD | TYPE III SQ YD |
| NUMBER OF PATCHES | 35 | 3 |
| BEGINNING STA. 1505+00 TO ENDING STA. 126+80 (JOB LIMITS) | 286.00 | 59.00 |
| TOTALS | 286 | 59 |

* SEE LINE DIAGRAM FOR PATCHING UNITS