

TABULATION OF RESURFACING QUANTITIES

LOCATION	TYPICAL SECTION	ROADWAY WIDTH	HMA SHOULDER WIDTH (EXIST. & PROP.)		AGGREGATE SHOULDER WIDTH		HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2 IN	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N50	HMA SURFACE COURSE, MIX "D", N50	HMA SHOULDER, 8 IN	AGGREGATE SHOULDERS TYPE B	AGGREGATE SHOULDER REMOVAL	SHOULDER RUMBLE STRIP				
			LT	RT	LT	RT														
			FT	FT	FT	FT											SQ YD	SQ YD	SQ YD	TON
STA. 488+69.00 TO STA. 509+37.00	1	26			4	4			5,974.22	2.39		501.83		628.67						
STA. 509+37.00 TO STA. 514+00.00	6	26	4			4			1,543.33	0.62		129.64		70.38						
STA. 514+00.00 TO STA. 535+32.00	1	26			4	4			6,159.11	2.46		517.37		648.13						
STA. 535+32.00 TO STA. 537+00.00	2	26			4	4			485.33	0.19		40.77		51.07						
STA. 537+00.00 TO STA. 544+59.00	2	26	4	4					2,192.67	1.15		184.18	674.67	57.68	149.93	1518.00				
STA. 544+59.00 TO STA. 545+00.00	1	26	4	4					118.44	0.06		9.95	36.44	3.12	8.10	82.00				
STA. 545+00.00 TO STA. 562+32.00	1	26			4	4			5,003.56	2.00		420.30		526.53						
STA. 562+32.00 TO STA. 563+83.00	2	26			4	4			436.22	0.17		36.64		45.90						
STA. 563+83.00 TO STA. 567+67.00	2	26	4	4					1,109.33	0.58		93.18	341.33	29.18	75.85	768.00				
STA. 567+67.00 TO STA. 568+35.00	2	26			4	4			196.44	0.08		16.50		20.67						
STA. 568+35.00 TO STA. 569+00.00	2	26	4						187.78	0.09		15.77	28.89	4.94	6.42	65.00				
STA. 569+00.00 TO STA. 572+16.00	2	26	4	4					912.89	0.48		76.68	280.89	24.02	62.42	632.00				
STA. 572+16.00 TO STA. 573+37.00	3	26	4	4					457.11	0.18		38.40		9.20						
STA. 573+37.00 TO STA. 576+48.00	3	26	4	4					1,174.89	0.47		98.69		23.64						
STA. 576+48.00 TO STA. 576+98.00	6	26	4			4			166.67	0.07		14.00		7.60						
STA. 576+98.00 TO STA. 578+87.00	1	26			4	4			546.00	0.22		45.86		57.46						
STA. 578+87.00 TO STA. 579+49.00	6	26	4			4			206.67	0.08		17.36		9.42						
STA. 579+49.00 TO STA. 586+66.00	3	26	4	4					2,708.67	1.08		227.53		54.49						
STA. 586+66.00 TO STA. 587+36.00	6	26	4			4			233.33	0.09		19.60		10.64						
STA. 587+36.00 TO STA. 589+90.00	1	26			4	4			733.78	0.29		61.64		77.22						
STA. 589+90.00 TO STA. 590+30.00	8	26		4					133.33	0.05		11.20		3.04						
STA. 590+30.00 TO STA. 592+34.00	5	26		4	4				680.00	0.27		57.12		31.01						
STA. 592+34.00 TO STA. 593+53.00	8	26		4	4				396.67	0.16		33.32		18.09						
STA. 593+53.00 TO STA. 594+52.91	8	26	4	4					377.44	0.15		31.70		7.59						
STA. 594+52.91 TO STA. 594+82.91	BUTT JOINT	26	7	7	4	4	133.33	22.22		0.05		11.20		9.12						
STA. 594+82.91 TO STA. 596+66.12									NIXON RUN CREEK S.N. 072-0164											
STA. 596+66.12 TO STA. 596+96.12	BUTT JOINT	26	7	7	4	4	133.33	22.22		0.05		11.20		9.12						
STA. 596+96.12 TO STA. 601+85.00	5	26		4	4				1,629.60	0.65		136.89		74.31						
STA. 601+85.00 TO STA. 612+95.00	3	26	4	4					4,193.33	1.68		352.24		84.36						
STA. 612+95.00 TO STA. 613+11.00	5	26		4	4				53.33	0.02		4.48		2.43						
STA. 613+11.00 TO STA. 656+62.00	1	26			4	4			12,569.56	5.03		1055.84		1322.70						
STA. 656+62.00 TO STA. 659+10.00	3	26	4	4					936.89	0.37		78.70		18.85						
STA. 659+10.00 TO STA. 664+77.00	5	26		4	4				1,890.00	0.76		158.76		86.18						
STA. 664+77.00 TO STA. 669+59.00	1	26			4	4			1,392.44	0.56		116.97		146.53						
STA. 669+59.00 TO STA. 672+86.00	2	26			4	4			944.67	0.38		79.35		99.41						
STA. 672+86.00 TO STA. 673+00.00	7	26	4			4			46.67	0.02		3.92		2.13						
STA. 673+00.00 TO STA. 677+23.00	4	26	4	4					1,598.00	0.64		134.23		32.15						
STA. 677+23.00 TO STA. 677+95.00	3	26	4	4					272.00	0.11		22.85		5.47						
STA. 677+95.00 TO STA. 683+69.00	6	26	4			4			1,913.33	0.77		160.72		87.25						
STA. 683+69.00 TO STA. 690+00.00	1	26			4	4			1,822.89	0.73		153.12		191.82						
STA. 690+00.00 TO STA. 691+73.00	1	26	4	4					499.78	0.26		41.98	153.78	13.15	34.17	346.00				
STA. 691+73.00 TO STA. 695+20.00	1	26	4	4					1,002.44	0.52		84.21	308.44	26.37	68.54	694.00				
STA. 695+20.00 TO STA. 702+05.00	11	26		4					1,978.89	0.91		166.23	304.44	52.06	67.65	685.00				

FILE NAME = 68961 - Phase II.dgn	USER NAME = johnsonvt	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/18/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.S. RTE. 1388	SECTION Z-UD-15DIRS-7(1V,E,2,4)RS-41	COUNTY PEORIA	TOTAL SHEETS 32	SHEET NO. 13
CONTRACT NO. 68961				
ILLINOIS FED. AID PROJECT				