

**SCHEDULE OF SIDE ROADS AND ENTRANCES**

LOCATION	AREA SQ YD	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2 IN	INCIDENTAL HMA SURFACING	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT	AGGREGATE SHOULDERS, TYPE B	AGGREGATE SURFACE CSE TYPE B
		SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON
<b>SIDE ROADS:</b>								
<b>CHRISTMAS LN.</b>								
STA. 34+36.00 TO STA. 34+87.00	348.50	26.67	13.33	321.83	29.27	0.14	15.50	
STA. 35+13.00 TO STA. 35+48.00	184.72	24.44	12.22	160.28	15.52	0.07	10.64	
<b>BELL SCHOOL RD. (CH 34)</b>								
STA. 44+38.00 TO STA. 44+87.00	258.61	30.00	15.00	228.61	21.72	0.10	14.90	
STA. 45+13.00 TO STA. 46+18.00	1,324.17	30.00	15.00	1,294.17	111.23	0.53	31.92	
<b>PULSIFER RD. (CH 69)</b>								
STA. 53+95.00 TO STA. 54+87.00	1,139.78	33.33	16.67	1,106.44	95.74	0.46	27.97	
STA. 55+13.00 TO STA. 55+93.00	546.67	26.67	13.33	520.00	45.92	0.22	24.32	
<b>MAHER RD.</b>								
STA. 65+13.00 TO STA. 67+27.00	1,914.11	35.56	17.78	1,878.56	160.79	0.77	65.06	
<b>OAKHILL CEMETERY RD.</b>								
STA. 84+17.00 TO STA. 84+87.00	435.56	28.89	14.44	406.67	36.59	0.17	21.28	
STA. 85+13.00 TO STA. 85+67.00	384.00	28.89	14.44	355.11	32.26	0.15	16.42	
<b>BROAD ST.</b>								
STA. 94+12.00 TO STA. 94+87.00	625.00	33.33	16.67	591.67	52.50	0.25	22.80	
<b>TEXAS RD.</b>								
STA. 101+97.00 TO STA. 104+87.00	3,947.22	50.00	25.00	3,897.22	331.57	1.58	88.16	
<b>MCINTYRE RD./ WOLFORD RD.</b>								
STA. 114+40.00 TO STA. 114+87.00	305.50	26.67	13.33	278.83	25.66	0.12	14.29	
STA. 115+13.00 TO STA. 115+76.00	525.00	26.67	13.33	498.33	44.10	0.21	19.15	
<b>EDEN RD.</b>								
STA. 123+37.00 TO STA. 124+87.00	1,391.67	24.44	12.22	1,367.22	116.90	0.56	45.60	
STA. 125+13.00 TO STA. 126+02.00	370.83	15.56	7.78	355.28	31.15	0.15	27.06	
<b>ROCKHILL RD/ TOWNHOUSE RD.</b>								
STA. 133+82.00 TO STA. 134+87.00	1,137.50	26.67	13.33	1,110.83	95.55	0.46	31.92	
STA. 135+13.00 TO STA. 136+81.00	1,950.67	26.67	13.33	1,924.00	163.86	0.78	51.07	
<b>CUTOFF RD.</b>								
STA. 10+13.00 TO STA. 10+72.00	458.89	26.67	13.33	432.22	38.55	0.18	17.94	
STA. 25+13.00 TO STA. 25+63.00	358.33	26.67	13.33	331.67	30.10	0.14	15.20	
<b>KRAMM RD.</b>								
STA. 155+13.00 TO STA. 155+71.00	402.78	26.67	13.33	376.11	33.83	0.16	17.63	
<b>MADER RD.</b>								
STA. 900+13.00 TO STA. 900+89.00	451.78	17.78	8.89	434.00	37.95	0.18	23.10	
<b>COTTONWOOD RD.</b>								
STA. 1023+57.00 TO STA. 1024+87.00	2,361.67	35.56	17.78	2,326.11	198.38	0.94	39.52	
STA. 1025+13.00 TO STA. 1025+66.00	341.56	26.67	13.33	314.89	28.69	0.14	16.11	
<b>TAYLOR RD.</b>								
STA. 1053+47.68 TO STA. 1054+67.68	2,366.67	37.78	18.89	2,328.89	198.80	0.95	36.48	
<b>KICKAPOO-EDWARDS RD.</b>								
STA. 1050+13.00 TO STA. 1051+08.00	1,551.67	35.56	17.78	1,516.11	130.34	0.62	28.88	
<b>ENTRANCES AND MAILBOX TURNOUTS</b>								
<b>PRIVATE ENTRANCES:</b>								
HMA -	52	750.88		750.88	63.07	0.30		
AGGREGATE -	34	490.96						111.94
PCC -	30	433.20						
<b>FIELD ENTRANCES:</b>								
AGGREGATE -	75	1,083.00						246.92
<b>MAILBOX TURNOUTS:</b>								
HMA -	43	620.92		620.92	52.16	0.25		
AGGREGATE -	3	43.32						9.88
<b>SUBTOTAL</b>								
		727.78	363.89	25,726.86	2,222.19	10.58	722.91	368.74
<b>TOTAL</b>		<b>728</b>	<b>364</b>	<b>25,727</b>	<b>2,222</b>	<b>11</b>	<b>723</b>	<b>369</b>

**PRIME COAT CONVERSION FACTORS**

SURFACE TYPE	BIT PR COAT	AGG PR COAT
	(GAL/SQ YD)	(LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW HMA COURSES	0.03	2

**HMA & AGGREGATE CONVERSION FACTORS**

SURFACE TYPE	LB	TON
	SQ YD IN	CU YD
HMA COURSES	112	2.016
COARSE AGGREGATE	114	2.05
FINE AGGREGATE		1.5

**MATERIAL TRANSFER DEVICE**

LOCATION	TON
POLYMERIZED HMA SURFACE CSE	1,744
HMA SURFACE CSE	14,584
<b>TOTAL</b>	<b>16,328</b>

**RUMBLE STRIP**

LOCATION	SQ FT
STA. 178+03 TO STA. 186+28	900.00
<b>TOTAL</b>	<b>900</b>

**MOWING**

LOCATION	UNIT
IL 8	1,275
<b>TOTAL</b>	<b>1,275</b>

FILE NAME = 68961 - Phase II.dgn

USER NAME = johnsantv  
 PLOT SCALE = 100.0000' / IN.  
 PLOT DATE = 3/18/2018

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: SHEET NO. 4 OF 6 SHEETS STA. TO STA.

F.A.S. RTE. 1388 SECTION IZ-1(D-15)RS-7(1)V,E,2,4)RS-4) COUNTY PEORIA TOTAL SHEETS 32 SHEET NO. 15 CONTRACT NO. 68961 [ILLINOIS] FED. AID PROJECT