

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Cleaning & painting of the existing steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All beams, bearings, and all other structural steel shall be cleaned per Near White Blast Cleaning – SSPC SP 10 according to the following schedule.

Bridge 1 – 3 – Entire Structure

**The designated paint system shall be Paint System 5 – MCU.
The final finish coat for the interior and exterior shall be according to the following schedule:**

Bridge No. 1 – 3 – Paint system 5 shall be used and all exterior fascias including the bottom of the bottom flanges shall be blue (Munsell No. 10B 3/6). All of the underside shall be painted Light Gray (Munsell No. 5B 7/1).

LOCATION 3 – THIS STRUCTURE WAS WIDEN IN THE MID 70'S FOR A TOTAL OF 7 BEAM LINES, VIEW ALL PLAN SHEETS FOR BEAM SIZES.

QP1 & QP2 IS REQUIRED FOR THIS CONTRACT.

AIR MONITORS – None for this project

FILE NAME = Copy of 68398.dgn	USER NAME = ing11stj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			(45-VNB-1)-1.2.(23-BR)-1	VARIOUS	16	4	
		CHECKED -	REVISED -			CONTRACT NO. 68975				
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				