

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	TOTAL QTY.	PEORIA COUNTY								TAZEWELL COUNTY							
				CONST. TYPE CODE Y031-1F 100% STATE 0% CITY URBAN (6 LOCATIONS)	CONST. TYPE CODE Y031-1F 95% STATE 5% CITY URBAN (2 LOCATIONS) PEORIA	CONST. TYPE CODE Y031-1F 93.3% STATE 6.7% CITY URBAN (2 LOCATIONS) PEORIA	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (2 LOCATIONS) BARTONVILLE	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (3 LOCATIONS) CHILlicoTHE	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (5 LOCATIONS) PEORIA	CONST. TYPE CODE Y031-1F 50% STATE 50% CITY URBAN (3 LOCATIONS) MAINTENANCE PEORIA	CONST. TYPE CODE Y031-1F 0% STATE 100% CITY URBAN (1 LOCATION) BARTONVILLE	CONST. TYPE CODE Y031-1F 100% STATE 0% CITY URBAN (8 LOCATIONS)	CONST. TYPE CODE Y031-1F 93.3% STATE 6.7% CITY URBAN (1 LOCATION) NORTH PEKIN	CONST. TYPE CODE Y031-1F 93.3% STATE 6.7% CITY URBAN (1 LOCATION) PEKIN	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (1 LOCATION) CREVE COEUR	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (3 LOCATIONS) MORTON	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (3 LOCATIONS) PEKIN	CONST. TYPE CODE Y031-1F 90% STATE 10% CITY URBAN (3 LOCATIONS) WASHINGTON	CONST. TYPE CODE Y031-1F 0% STATE 100% CITY URBAN (2 LOCATIONS) WASHINGTON
67100100	MOBILIZATION	L SUM	1.0	0.15	0.05	0.05	0.05	0.08	0.06			0.20	0.03	0.03	0.03	0.07	0.07	0.08	0.05
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.15	0.05	0.05	0.05	0.08	0.06			0.20	0.03	0.03	0.03	0.07	0.07	0.08	0.05
72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	18.0					18.0											
80501000	SERVICE INSTALLATION (SPECIAL)	EACH	1.0							1.0									
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2476.0					2476.0											
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4.0					4.0											
88800100	PEDESTRIAN PUSH-BUTTON	EACH	54.0			4.0	6.0	18.0	4.0						4.0	2.0	16.0		
89502105	REBUILD EXISTING SIGNAL HEAD, LED	EACH	20.0					20.0											
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	3.0					3.0											
X0324134	BATTERY BACKUP SYSTEM WITH CABINET	EACH	3.0					3.0											
X0326101	BOND TRAFFIC SIGNAL STRUCTURE	EACH	380.0	57.0	18.0	18.0	17.0	24.0	46.0		3.0	74.0	8.0	9.0	7.0	24.0	22.0	34.0	19.0
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	10631.0	1961.0	446.0	257.0	431.0	388.0	1425.0		126.0	2790.0	378.0	314.0	168.0	463.0	100.0	877.0	507.0
X8950200	REBUILD EXISTING HANDHOLE	EACH	2.0							2.0									

STATE OF ILLINOIS
DEPARTMENT
OF TRANSPORTATION

**SUMMARY OF QUANTITIES
(PEORIA COUNTY)**

SCALE: NONE

STA. _____ TO STA. _____

ROUTES	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VARIOUS (VARIOUS)	D4 SIGNAL WORK 2010-2	VARIOUS	9	3
CONTRACT NO. 68983				