COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

S:\GEN\DRAFT\STD&PLNS\SQUADA\BRIDGE CONTRACTS\STEEL BEAM REP\CedarSt&Bridge SN090-0030\SN090-0030.dgn

SN.090-0030 CEDAR ST.
BRIDGE OVER IL. RIVER

FILE NAME = SN090-0030.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS & GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - CEJ	REVISED - ___			669	103B-I-6	PEO.. .	18	2
	PLOT SCALE = 103.9367 ' / IN.	CHECKED - ___	REVISED - ___			MISC. STEEL TRUSS REPAIRS		CONTRACT NO. 68987		
	PLOT DATE = 3/26/2010	DATE - 03/26/2010	REVISED - ___		SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____	FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		