

## SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAS 514 (ALLEN STREET)  
 CHAMPAIGN COUNTY  
 S.N. 010-8130  
 STA. 356+17.00  
 TO  
 STA. 356+39.00  
 RURAL 2-LANE  
 100% STATE  
 Y007

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
20700220	POROUS GRANULAR EMBANKMENT	CU YD	19.0
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100.0
* 25000210	SEEDING, CLASS 2A	ACRE	0.2
* 25000350	SEEDING, CLASS 7	ACRE	0.2
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18.0
* 25100115	MULCH, METHOD 2	ACRE	0.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20.0
28000305	TEMPORARY DITCH CHECKS	FOOT	69.0
28000400	PERIMETER EROSION BARRIER	FOOT	324.0
28000500	INLET & PIPE PROTECTION	EACH	1.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	16.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6.0
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	52.0
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	16.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50104400	CONCRETE HEADWALL REMOVAL	EACH	2.0
50105220	PIPE CULVERT REMOVAL	FOOT	17.0
51500100	NAME PLATES	EACH	1.0

FILE NAME =	USER NAME = hennessdm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cs:\proj_work\1PWIDOT\HENNESSDM\dms86853\070619-shr-500.dgn		DRAWN -	REVISED -		514	81-15D,CR	CHAMPAIGN	30	4				
PLOT SCALE = 48,0000' / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 70619				
PLOT DATE = 3/1/2010		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								