

# SCHEDULES OF QUANTITIES

## EXPLORATION TRENCH, 52" DEPTH (21301052)

STATION	STATION	LENGTH (FT)
355+89.00 LT	356+39.00 LT	50.0
355+89.00 RT	356+39.00 RT	50.0
TOTAL =		100.0

## AGGREGATE SURFACE COURSE, TYPE B (40200800)

STATION	LENGTH (FT)	WIDTH (FT)	DEPTH (IN)	TONS
355+75.00 RT	23.0	16.0	6.0	16.0
TOTAL =				16.0

## BITUMINOUS MATERIALS (PRIME COAT) (40600100)

STATION	STATION	SQ YDS	GALLONS
356+17.00	356+39.00	52.0	5.2
TOTAL =			6.0

## AGGREGATE SHOULDERS, TYPE B, 4" (48101498)

STATION	STATION	LENGTH (FT)	WIDTH (FT)	SQ YDS
356+17.00 LT	356+39.00 LT	24.0	3.0	8.0
356+17.00 RT	356+39.00 RT	24.0	3.0	8.0
TOTAL =				16.0

## CONCRETE HEADWALL REMOVAL (50104400)

STATION	OFFSET	EACH
356+02.50	23.0' RT	1.0
356+19.00	23.0' RT	1.0
TOTAL =		2.0

## PIPE CULVERT REMOVAL (50105220)

STATION	OFFSET	FEET
356+11.00	23.0' RT	17.0
TOTAL =		17.0

## NAME PLATES (51500100)

STATION	OFFSET	EACH
356+24.00	19.0' RT	1.0
TOTAL =		1.0

## BOX CULVERT END SECTION, CULVERT NO. 1 (54001001)

STATION	OFFSET	EACH
356+28.00	17.0' LT	1.0
356+28.00	16.0' RT	1.0
TOTAL =		2.0

## END SECTIONS, 15" (54213450)

STATION	OFFSET	EACH
355+59.50	23.0' RT	1.0
355+90.50	23.0' RT	1.0
TOTAL =		2.0

## PIPE CULVERTS, CLASS D, TYPE 1, 15" (542D0220)

STATION	STATION	LENGTH (FT)
355+59.50 RT	355+90.50 RT	31.0
TOTAL =		31.0

## PAINT PAVEMENT MARKING - LINE 4" (78001110)

WHITE -			
STATION	STATION	LOCATION	FEET
356+17.00	356+27.00	9.0' LT	10.0
356+17.00	356+37.00	10.0' RT	20.0
SUBTOTAL =			30.0

## YELLOW -

STATION	STATION	LOCATION	FEET
356+17.00	356+39.00	SKIP-DASH	5.5
GRAND TOTAL =			36.0

## REMOVE WOOD POST (X0300247)

STATION	OFFSET	EACH
356+16.38	27.04' LT	1.0
TOTAL =		1.0

## REMOVE EXISTING MONUMENT (XX006084)

STATION	OFFSET	EACH
356+15.00	27.82' LT	1.0
TOTAL =		1.0