

SUMMARY OF QUANTITIES (SHEET 1 OF 3)

LOCATION OF WORK: FAP ROUTE 332
 VERMILION COUNTY
 ROADWAY IMPROVEMENTS
 STA. 2743+00.00 TO STA. 2911+70.00
~~URBAN MULTILANE~~
 FUNDING BREAKOUT: 80% FEDERAL / 20% STATE
 CONSTRUCTION TYPE CODE: I000-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,645.0
40600300	AGGREGATE (PRIME COAT)	TON	193.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	4,415.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT- MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	2,190.0
40600990	TEMPORARY RAMP	SQ YD	201.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	8,000.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	220.0
40800030	AGGREGATE (PRIME COAT)	TON	5.0
40800050	INCIDENTAL HOT- MIX ASPHALT SURFACING	TON	190.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,215.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	66,075.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	29,150.0
45100200	CRACK FILLING	POUND	8,200.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	35.0
48203100	HOT-MIX ASHALT SHOULDERS	TON	110.0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	13.0
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	7.0