

## SUMMARY OF QUANTITIES (cont.)

CODE NO	ITEM	UNIT	LOCATION OF WORK:		
			URBAN TOTAL	FAP 800	INTERCONNECT
CONSTRUCTION TYPE CODE:			100% STATE	100% STATE	100% CITY
			Y031-1F	Y031-1F	Y031-1F
			QUANTITY	QUANTITY	QUANTITY
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2.0	2.0	
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2.0	2.0	
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6.0	6.0	
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1.0	1.0	
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	10.0	10.0	
88500100	INDUCTIVE LOOP DETECTOR	EACH	8.0	8.0	
88600100	DETECTOR LOOP, TYPE I	FOOT	880.0	880.0	
88700200	LIGHT DETECTOR	EACH	2.0		2.0
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1.0		1.0
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1.0	1.0	
89502380	REMOVE EXISTING HANDHOLE	EACH	6.0	6.0	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10.0	10.0	
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	638.0	638.0	
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	465.0		465.0
X8800101	PEDESTRIAN PUSH-BUTTON, SPECIAL	EACH	8.0	8.0	
82106825	LUMINAIRE, METAL HALIDE HORIZONTAL MOUNT 400 WATT	EACH	4.0		4.0

FILE NAME *	USER NAME * biggerd	DESIGNED - BDB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	F.A.P. RTE. 800	SECTION (288)IS	COUNTY CHAMPAIGN	TOTAL SHEETS 13	SHEET NO. 5
c:\pwwork\PK1001\BIGGSRD\dms85873\787	5_signals.dgn	DRAWN - BDB	REVISED -	SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 70735 ILLINOIS FED. AID PROJECT		
PLOT SCALE = 20.0000' / IN.		CHECKED -	REVISED -						
PLOT DATE = 3/25/2010		DATE -	REVISED -						