

48203100 HOT-MIX ASPHALT SHOULDERS (CONTD)

	STATION	TO	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	THICKNESS INCHES	HMA SHLD TONS	40600115 POLY BIT MATLS PR CT GAL	40600300 AGG PR CT TON
I-74 RAMPS										
RAMP A	0+34.30		7+61.00	726.7	8.0	656.7	2.5	91.9	65.7	1.3
RAMP A	0+34.30		7+61.00	726.7	4.0	328.3	2.5	46.0	32.8	0.7
RAMP B	7+43.00		22+33.30	1490.3	8.0	1427.8	2.5	199.9	142.8	2.9
RAMP B	7+43.00		22+33.30	1490.3	4.0	713.9	2.5	99.9	71.4	1.4
RAMP C	0+32.80		5+92.00	559.2	8.0	1073.3	2.5	150.3	107.3	2.1
RAMP C	0+32.80		5+92.00	559.2	4.0	536.7	2.5	75.1	53.7	1.1
RAMP D	7+62.00		22+40.94	1478.9	8.0	1433.7	2.5	200.7	143.4	2.9
RAMP D	7+62.00		22+40.94	1478.9	4.0	716.8	2.5	100.4	71.7	1.4
SUB-TOTAL =								964.2	688.7	13.8

SIDEROADS

NBL	OLD PEORIA CT	RT	-	4.0	64.0	2.5	9.0	6.4	0.1	
NBL	OLD PEORIA CT	LT	-	4.0	80.1	2.5	11.2	8.0	0.2	
SBL	OLD PEORIA CT	RT	-	4.0	91.0	2.5	12.7	9.1	0.2	
SBL	OLD PEORIA CT	LT	-	4.0	53.0	2.5	7.4	5.3	0.1	
SBL	OLD PEORIA RD	RT	-	4.0	60.2	2.5	8.4	6.0	0.1	
SBL	OLD PEORIA RD	LT	-	4.0	76.0	2.5	10.6	7.6	0.2	
SBL	T.R. 154	RT	-	4.0	70.0	2.5	9.8	7.0	0.1	
SBL	T.R. 154	LT	-	4.0	64.0	2.5	9.0	6.4	0.1	
NBL	T.R. 215	RT	-	4.0	79.3	2.5	11.1	7.9	0.2	
NBL	T.R. 215	LT	-	4.0	99.0	2.5	13.9	9.9	0.2	
SBL	T.R. 215	RT	-	4.0	89.5	2.5	12.5	9.0	0.2	
SBL	T.R. 215	LT	-	4.0	93.0	2.5	13.0	9.3	0.2	
SBL	MABLE RD	RT	-	10.0	135.1	2.5	18.9	13.5	0.3	
SBL	MABLE RD	LT	-	10.0	167.4	2.5	23.4	16.7	0.3	
SUB-TOTAL =								171.0	122.2	2.4

TOTAL = 7167.4 5119.6 102.4

USE = 7167.0 5120.0 102.0

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -
ct:\pw\work\PWIDOT\SHERERJM\00109813\0570768-shr-schedule.dgn		DRAWN - JMS	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED - JMS	REVISED -
	PLOT DATE = 3/2/2010	DATE - 061709	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 4 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
676	(9-1,9)RS	MCLEAN	81	36
CONTRACT NO. 70768				
ILLINOIS FED. AID PROJECT				