

SUMMARY OF QUANTITIES

FAI-72
 CHAMPAIGN CO.
 RURAL
 INTERSTATE
 100% STATE
 MINOR
 STRUCTURE
 REPAIR

 SFTY-2A
 S.N. 010-0146

CODE NO	ITEM	UNIT	TOTAL QUANTITY
50157300	PROTECTIVE SHIELD	SQ YD	250.0
50500405	FURNISH AND ERECT STRUCTURAL STEEL	POUND	1090.0
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	10.0
50501130	STRUCTURAL STEEL REPAIR	POUND	430.0
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10.0
52100520	ANCHOR BOLTS, 1"	EACH	20.0
67100100	MOBILIZATION	L SUM	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0
X0321468	PLUG EXISTING DECK DRAINS	EACH	16.0
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	60.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DAY	28.0
Z0003600	BEAM STRAIGHTENING	L SUM	1.0
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	30.0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	23.0
NO SPECIALTY ITEMS			

FILE NAME =	USER NAME = simagn	DESIGNED - GMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\PWIDOT\SIH5GM\08184265\057065-05-08-Bridge Repair Plans.dgn	65-Bridge Repair Plans.dgn	DRAWN - GMS	REVISED -			72	(10-71HB)BDR,BJR	CHAMPAIGN	14	3	
PLOT SCALE = 40.0001' / IN.	CHECKED -	REVISED -				CONTRACT NO. 70865					
PLOT DATE = 2/26/2010	DATE -	REVISED -				FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					