

VARIOUS ROUTES

100% STATE

* F.A.P. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	4
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		CONTRACT NO. 72088		

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE									
				ROADWAY				TRAFFIC SIGNALS		LIGHTING		SIDEWALK	
				FAP 67	FAP 75	FAP 668	FAI 72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668
				1000-2A	Y03I-IF	Y030-IE	SFTY-IB						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	335	335									
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	65	65									
20200100	EARTH EXCAVATION	CU YD	13545	12065	777	703							
20800150	TRENCH BACKFILL	CU YD	2077	1841		236							
25000210	SEEDING, CLASS 2A	ACRE	3.0	3.0									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	465	435	15	15							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	465	435	15	15							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	465	435	15	15							
25100120	MULCH, METHOD 2	TON	18.5	17.5	0.5	0.5							
25200110	SODDING, SALT TOLERANT	SQ YD	14412	12381	948	1083							
25300500	TOP SOIL FOR PLANTING	CU YD	495	495									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	625	575	25	25							
28000305	TEMPORARY DITCH CHECKS	FOOT	420.5	420.5									
28000400	PERIMETER EROSION BARRIER	FOOT	3313	3313									
28000500	INLET AND PIPE PROTECTION	EACH	189	156	3	30							
30200650	PROCESSING MODIFIED SOIL 12"	SO YD	11832	11832									
31001500	LIME	TON	177	177									
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SO YD	18260	13096	2425	2739							
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1473	500	595	378							
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1012	507	271	234							
35300615 35501331	PORTLAND CEMENT CONCRETE BASE COURSE 11 3/4" HOT-MIX ASPHALT BASE COURSE, 11 3/4"	SO YD SO YD	443 7720	443 4943	1232	1545							
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	23	5	5	12						
40600300	AGGREGATE (PRIME COAT)	TON	218	114	23	23	58						
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2174	1319	448	407							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1405	700	283	230	192						
40600990	TEMPORARY RAMP	SO YD	354	155	45	38	116						
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2705	1009			1696						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	31	31									
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	5184	2749	672	631	1132						
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SO YD	14519	14519									
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	407	358	13	36							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	1278	825	239	214							
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	35462						27860	7602			
42400800	DETECTABLE WARNINGS	SO FT	488	463			25						

* DENOTES SPECIALTY ITEM

SHEET 1 OF 7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY MLO
 CHECKED BY SJR

DATE 08/05