

VARIOUS ROUTES

100% STATE

* F.A.I. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	8
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
			CONTRACT NO. 72088	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE															
				ROADWAY				TRAFFIC SIGNAL		LIGHTING		SIDEWALK							
				FAP 67	FAP 75	FAP 668	FAI 72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668						
* 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	4	4															
* 73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	8	6	2														
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	18623	14616	1731	2276													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5623	3089	1471	1063													
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1515	1515															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1009	657	52	300													
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	135		135														
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- <i>INLAID - LETTERS AND SYMBOLS</i>	SO FT	871.0	545.4	193.6	132.0													
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- <i>INLAID - LINE 5"</i>	FOOT	3824	1724	460	460	1180												
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- <i>INLAID - LINE 6"</i>	FOOT	2461	1652	216	513	80												
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- <i>INLAID - LINE 8"</i>	FOOT	3014	1121			1893												
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- <i>INLAID - LINE 12"</i>	FOOT	324	128			196												
* 78004260	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- <i>INLAID - LINE 24"</i>	FOOT	760	589	86	85													
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	568	267	75	78	148												
* 78200300	PRISMATIC CURB REFLECTOR	EACH	186	116	44	26													
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	568	267	75	78	148												
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	2					1	1										
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1						1										
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1354					1156	198										
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	19					3	16										
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	99					52	47										
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	35					24	11										
* 81020600	CONDUIT PUSHED, 2 1/2" DIA., INTERMEDIATE METAL	FOOT	1065						1065										
* 81020900	CONDUIT PUSHED, 4" DIA., INTERMEDIATE METAL	FOOT	126						126										
* 81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	FOOT	679					524	155										
* 81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	50					50											
* 81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	789	340				198	251										
* 81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	242					160	82										
* 81306100	<i>FUNCTION BOX (SPECIAL)</i>	EACH	5	5															
* 81400100	HANDHOLE	EACH	10					5	5										
* 81400300	DOUBLE HANDHOLE	EACH	2					1	1										
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA, POLYETHYLENE	FOOT	4574						4574										
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4705					1235	272	3198									
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	15						15										
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	8					4	4										
* 82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1						1										
* 83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	15						15										
* 83057120	<i>LIGHT POLE, WOOD, 25', CLASS 4</i>	EACH	2	2															
* 83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	15						15										

* DENOTES SPECIALTY ITEM

SHEET 5 OF 7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY MLO
 CHECKED BY SJK
 DATE 08/05