			VARIOUS ROUTES	100% STATE									
				CONSTRUCTION TYPE CODE									
				ROADWAY				TRAFFIC SIGNAL		LIGHTING		SIDEWALK	
				FAP 67	FAP 75	FAP 668	FAI72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668
PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A				Y031-1F		Y030-1E		SFTY-1B	
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	60							60			
84200804	REMOVAL OF POLE FOUNDATION	EACH	2							2			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2					1	1				
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	2					1	1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2					1	1				
87100160	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	FOOT	4676.5					4364	312.5				
87300705	ELECTRIC CABLE IN TRENCH, COMMUNICATION, NO. 18 3 PAIR	FOOT	1505					925	580				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	811					433	378				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1011					721	290				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3464					2311	1153				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2783					1801	982				
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	1301					809	492				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	30					17	13				
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	10					5	5				
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1						1				
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1						1				
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1						1				
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1						1				
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1						1				
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	2					2					
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1						1				
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1	1									
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	30					15	15				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	6					3	3				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10						10				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	95					45	50				
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21					21					
87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	2					2					
88020420	SIGNAL HEAD, POLYCARBONATE, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2						2				
88020510	SIGNAL HEAD, POLYCARBONATE, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1						1				
88020700	SIGNAL HEAD, POLYCARBONATE, 3-FACE, 2-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2						2				
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	26					16	10				
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	7					5	2				
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3-SECTION, 2-5-SECTION, BRACKET MOUNTED	EACH	5					4	1				
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4					2	2				

* F.A.I. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	9
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 72088

* DENOTES SPECIALTY ITEM

SHEET 6 OF 7

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY MLO
CHECKED BY SJK
DATE 08/05