

VARIOUS ROUTES

100% STATE

* F.A.P. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	10
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
		CONTRACT NO. 72088		

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE															
				ROADWAY				TRAFFIC SIGNAL		LIGHTING		SIDEWALK							
				FAP 67	FAP 75	FAP 668	FAI 72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668						
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4							2	2								
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	55							31	24								
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	11							6	5								
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1							1									
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2694							2694									
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1							1									
* 89502380	REMOVE EXISTING HANDHOLE	EACH	8							8									
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8							8									
XZ127902	RETAINING WALL, SPECIAL	SQ FT	1962	1000		962													
XZ177600	REMOVE EXISTING BUMPER BLOCKS	EACH	3	3															
X0301728	CONCRETE COLLAR, SPECIAL	CU YD	0.6	0.6															
* X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	2	2															
X0321690	BRICK WALL REMOVAL	FOOT	24	24															
X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	35	35															
X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	592	592															
X0322092	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	15	15															
X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	103	103															
X0323099	RETAINING WALL REMOVAL	CU YD	26	26															
* X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	1193							683	510								
X0323344	VANE DRAINS	FOOT	94	94															
X0324752	STORM SEWER TO BE FILLED	CU YD	71	71															
X0703200	CONCRETE ISLAND (SPECIAL)	SQ FT	2716	2716															
X4404000	PARKING LOT PAVEMENT REMOVAL	SO YD	7144	5967	131	1046													
X6050700	REMOVE INLET BOX	EACH	1	1															
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	3600	3600															
* X7330310	OVERHEAD SIGN STRUCTURE - SPAN, DUAL MONOTUBE	FOOT	321.0	209.8	111.2														
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	14138	5655								8483							
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	140									140							
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1															
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	3	3															
X0326875	TRENCHLESS PIPE INSTALLATION, 18"	FOOT	26	26															
X0326876	TRENCHLESS PIPE INSTALLATION, 24"	FOOT	43	43															
X0326877	TRENCHLESS PIPE INSTALLATION, 48"	FOOT	131	131															
* 02106700	LUMINAIRE, SDDULM VAPOR, HORIZONTAL MOUNT, 400WATT (MATERIAL ONLY)	EACH	2									2							
* 03004601	LIGHT POLE, ALUMINUM, 50 FT. H.H., 15 FT. DAVIT ARM (MATERIAL ONLY)	EACH	1										1						

* DENOTES SPECIALTY ITEM

SHEET 7 OF 7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 DRAWN BY MLO
 CHECKED BY SJK
 DATE 08/05