

c:\pwworking\pwidotbl\aughlinrl\0204163\stormsewer\Schedule.dgn
DATE

STORM SEWER TABLE															
STATION TO STATION	OFFSET	STORM SEWERS CLASS A													TRENCH BACKFILL CU YD
		12" TY 1	18" TY 1	24" TY 1	36" TY 1	48" TY 1	12" TY 2	18" TY 2	24" TY 2	30" TY 2	36" TY 2	42" TY 2	48" TY 2		
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
CLEAR LAKE AVE															
123+23.18	LT	7													2
125+25.00 - 125+25.00	LT	10													
130+67.50 - 130+71.36	LT							6							2
131+35.00 - 131+61.03	LT	35													5
20+05.38 - 21+00.00	LT				116										72
20+36.65 - 21+00.00	LT	74													11
21+00.00	LT							14							5
21+00.00 - 21+80.34	LT	80													23
25+13.00 - 25+58.00	LT	45													6
25+58.00	LT	10													1
26+58.10 - 26+84.38	LT										46				61
26+84.38 - 28+57.32	LT												190		245
27+85.00 - 28+57.32	LT	73													10
28+57.32 - 29+95.00	LT												135		
29+40.00 - 29+50.00	LT	10													1
29+50.00 - 29+95.00	LT	43													
29+95.00 - 30+30.71	LT				32										
30+30.71 - 31+71.84	LT				42										
31+67.57 - 31+70.00	LT	24													
33+80.00	LT	16													
21+50.00 - 22+00.00	CL	52													7
22+00.00 - 22+65.00	CL	67													9
22+65.00 - 23+00.00	CL	37													5
23+00.00 - 23+65.00	CL	66													11
23+65.00 - 24+12.36	CL	47													10
24+80.00 - 25+00.00	CL	23													3
25+00.00 - 25+88.00	CL	88													17
25+88.00 - 25+90.00	CL	9													2
25+93.51 - 25+94.00	CL	4													1
26+71.74 - 27+03.60	CL	40													5
28+04.00 - 28+45.09	CL	52													7
29+45.00 - 29+55.00	CL	10													1
29+55.00 - 29+60.00	CL	16													3
29+60.00 - 29+70.00	CL	10													1
31+50.00	CL			15											
32+00.00	CL	8													
33+50.00	CL	8													
34+50.00	CL	8													
131+82.83 - 132+00.66	RT	19													4
20+65.00 - 20+80.00	RT	47													6
21+33.88 - 21+35.00	RT	5													1
22+30.00 - 22+35.13	RT	10													2
23+50.00 - 25+36.00	RT	186													28
25+36.00 - 25+36.50	RT							7							2
25+36.00 - 26+05.39	RT	71													14
29+60.00 - 29+70.00	RT	10													1
29+60.00 - 29+52.18	RT		35												
29+95.00	RT					15									
31+50.00	RT			17											
FAP 67 SUB-TOTAL		1320	35	106	116	15	27	0	0	0	0	46	325	584	
RE-ALIGNED HILL ST															
0+80.00 - 0+90.00	LT	10													1
0+90.00 - 1+10.06	LT	25													6
0+90.00 - 1+02.76	LT&RT	53													7
0+95.00 - 1+05.00	RT	10													1
1+02.76 - 1+05.00	RT	8													1
1+02.76 - 2+92.89	RT											190			160
2+92.89 - 4+10.00	RT											118			163
4+10.00	LT&RT									54					50
4+10.00	LT&RT									12					27
4+10.00 - 4+25.00	LT	15													4
4+10.00 - 7+50.00	RT										332				
7+50.00 - 8+25.00	RT	71													13
8+25.00	LR&RT	30													7
7+50.00 - 9+00.00	RT										136				
9+00.00 - 9+25.00	RT	25													9
9+00.00	LT&RT										58				83
9+00.00 - 9+75.00	LT										82				
9+25.00	LT&RT	30													7
9+75.00 - 10+50.00	LT										82				
10+35.00 - 10+50.00	RT	15													3
10+35.00 - 10+50.00	LT							15							4
10+50.00	LT	20													3
10+50.00	LT&RT	30													8
10+50.00 - 11+50.00	LT									110					
11+50.00 - 11+75.00	LT	33													5
11+75.00	LT&RT	30													7
FAP 67 SUB-TOTAL		405	0	0	0	0	15	0	176	0	690	308	0	569	

F.A.P. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	SANGAMON	363	107
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 72088				

TRENCH BACKFILL

STATION TO	STATION	OFFSET	CU YD
21+00.00	22+80.00	LT	58
22+80.00	23+35.00	LT	23
23+35.00	25+58.00	LT	165
25+58.00	26+75.00	LT	124
26+75.00	26+84.38	LT	21
0+42.00	0+42.00	LT&RT	15
TOTAL			406

QUANTITIES GIVEN FOR PIPE CULVERTS
SEE SHEET 108 FOR STORM SEWER TRENCH BACKFILL TOTALS

* IF REQUIRED DUE TO FINAL VERTICAL CLEARANCE A QUANTITY FOR "STORM SEWER (WATERMAIN REQUIREMENT)" HAS BEEN INCLUDED FOR THIS STORM SEWER.

SHEET 4 OF 5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DATE 08/05

DRAWN BY MLO
CHECKED BY CWG