

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	108
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 72088				

STORM SEWER TABLE															
STATION TO STATION	OFFSET	STORM SEWERS CLASS A												TRENCH BACKFILL CU YD	
		12" TY 1	18" TY 1	24" TY 1	36" TY 1	48" TY 1	12" TY 2	18" TY 2	24" TY 2	30" TY 2	36" TY 2	42" TY 2	48" TY 2		
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
RE-ALIGNED HILL ST (CONT'D)															
11+50.00 - 12+25.00	LT									75					
12+25.00 - 13+00.00	LT							66							
13+00.00	LT	20													4
13+00.00	LT&RT	30													7
13+00.00 - 14+00.00	LT							88							
14+00.00 - 15+00.00	LT							90							
15+00.00 - 16+00.00	LT							90							
16+00.00 - 17+00.00	LT							94							35
17+00.00	LT&RT							30							15
17+00.00 - 17+50.00	LT							50							19
17+50.00 - 17+84.00	LT	34													5
17+00.00 - 17+84.00	RT	84													20
FAP 67 SUB-TOTAL		168	0	0	0	0	0	174	334	75	0	0	0	0	105
NORTH FRONTAGE RD															
1+40.00 - 1+47.00	RT	10													1
1+47.00 - 1+94.00	RT	65													11
1+94.00 - 2+80.00	RT	86													
2+80.00 - 2+90.00	RT							12							3
2+90.00	LT&RT							48							14
2+80.00 - 2+90.00	LT							10							3
2+90.00 - 3+12.08	LT							28							18
3+79.62 - 6+00.00	LT									110					
6+00.00	LT	8													
6+00.00 - 6+50.00	LT							54							16
6+00.00 - 7+00.00	LT									98					
6+50.00	LT&RT							30							8
6+50.00 - 6+60.00	LT							10							3
6+50.00 - 6+60.00	RT	10													2
7+00.00 - 8+00.00	LT			95											
8+00.00	LT	18													3
8+00.00	LT&RT	30													7
8+00.00 - 8+50.00	LT		50												
FAP 67 SUB-TOTAL		227	50	95	0	0	0	192	0	208	0	0	0	0	89
SOUTH FRONTAGE RD															
10+48.19 - 12+00.00	LT	147													
11+57.46 - 12+05.08	RT							50							14
12+00.00	LT&RT	26													3
12+00.00	LT	44													
12+97.79 - 13+34.67	LT			37											
13+37.36 - 13+40.00	LT		17												
13+30.00 - 13+40.00	LT		10												1
13+40.00	LT&RT							26							9
13+30.00 - 13+40.00	RT		10												1
12+05.08 - 12+52.61	RT		50												14
12+52.61 - 13+08.58	RT		50												15
13+08.58 - 13+58.58	RT		50												17
13+40.00 - 13+58.58	RT							29							
13+41.34 - 13+61.98	LT					32									14
FAP 67 SUB-TOTAL		217	187	37	0	32	50	55	0	0	0	0	0	0	88
DIRKSEN PARKWAY															
164+79.50 - 164+73.70	LT	9													1
166+61.87 - 166+64.06	LT	12													2
167+83.59	LT	9													2
169+25.84 - 169+26.08	LT	5													
170+61.55 - 170+61.86	LT	5													
164+89.00 - 165+76.36	RT									88					63
165+76.36	RT	8													1
165+76.36 - 166+09.94	RT	35													6
165+76.36 - 166+70.46	RT									94					71
166+70.46	RT	6													1
166+70.46 - 167+70.00	RT									100					86
167+70.00	RT	15													2
168+95.00 - 168+98.97	RT	4													1
FAP 668 SUB-TOTAL		108	0	0	0	0	0	0	0	194	88	0	0	0	236
FAP 67 TOTAL		2337	272	238	116	47	458	389	459	0	690	354	325		1435
FAP 668 TOTAL		108	0	0	0	0	0	0	0	194	88	0	0	0	236
GRAND TOTAL		2445	272	238	116	47	458	389	459	194	778	354	325		1671

SEE SHEET 107
 FOR TRENCH BACKFILL
 TOTALS AT PIPE CULVERTS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DATE 08/05
 DRAWN BY MLO
 CHECKED BY CWG

c:\pwworkspace\pwidot\blaughlinrld\01834468\StormSewerSchedule.dgn *DATE*