

CODE NO.	ITEM	UNITS	TOTAL QUANTITY 100% STATE	CONSTRUCTION CODE					
				BROWN COUNTY			SCHUYLER COUNTY		
				ROADWAY HMA RESURFACING STA. 52+00 TO STA. 420+00.00	ROADWAY NEW CONSTRUCTION STA. 420+00.00 TO STA. 434+34.07	BRIDGE SN 005-0000 STA. 434+34.07 TO STA. 439+03.24	ROADWAY NEW CONSTRUCTION STA. 439+03.24 TO STA. 452+80.20 BK. = STA. 452+78.48 AH. TO STA. 454+00.00	ROADWAY HMA RESURFACING STA. 454+00.00 TO STA. 459+53.00	ROADWAY HMA RESURFACING STA. 459+53.00 TO STA. 469+00.00 AND IL103 INTERSECTION
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12880	11042	522		522	166	628
70300250	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	98848	85864	3855		3883	692	4554
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	348						348
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	63						63
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	388						388
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1461	1227	72.5		72.5	19	70
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	175						175
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	29						29
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1				1		
72400710	RELOCATE SIGN PANEL - TYPE 1	SO FT	20		10		10		
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	3707						3707
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	288						288
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	388						388
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	175						175
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	94847	85864	3855		3883	692	553
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LETTERS AND SYMBOLS	SO FT	63						63
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 5"	FOOT	294						294
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 6"	FOOT	60						60
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 24"	FOOT	29						29
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	562	461	22		22	8	49
78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	4	8		8		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4	2		2		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	519	461	10		10	8	30
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION (COMPLETE)	EACH	1						1
X0321100	GEOTEXTILE RETAINING WALL	SO FT	300			300			
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4			4			
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SO FT	1129			1129			
X2020500	EARTH EXCAVATION (ROCKFILL)	CU YD	670				670		
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	89						89
X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	2						2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		0.5		0.5		
Z0022800	FENCE REMOVAL	FOOT	404		125		279		
Z0054530	ROCK FILL - SUBGRADE	TON	350				350		
X0326911	TRANSVERSE DRAINS COMPLETE	EACH	5		3		2		
X0325195	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SO YD	290	290					

* SPECIALTY ITEM

• 9RS-4, (10,11)RS-3; (10B-1)R
 ** BROWN, SCHUYLER

FILE NAME =	USER NAME = loughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6:\pwwork\PIWIDOT\LAUGHLINRL\dms28637\672432-shr+seq.dgn	PLOT SCALE = 180.0000' / IN.	DRAWN -	REVISED -					31T			196	8
PLOT DATE = Mar-26-2010 12:54:42PM	DATE -	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 72432				
		DATE -	REVISED -					ILLINOIS FED. AID PROJECT				