

| BITUMINOUS SHOULDER SCHEDULE | | | | | | |
|--|----------------|---------------|---|---|--|--|
| LOCATION STATION TO STATION | LENGTH (FT) | WIDTH (FT) | HOT-MIX ASPHALT REMOVAL (VAR. DEPTH) (SQ YD) | HOT-MIX ASPHALT REMOVAL (2 1/4") (SQ YD) | HOT-MIX ASPHALT SHOULDERS (2 1/4") (TON) | HOT-MIX ASPHALT SHOULDERS (8") (SQ YD) |
| FAP 317 (US 24) | | | | | | |
| RT. STA. 76+56.68 TO RT. STA. 81+68.70 | 512.02 | 3.0 | 171 | | 21.5 | |
| LT. STA. 76+56.68 TO LT. STA. 81+68.70 | 512.02 | 3.0 | 171 | | 21.5 | |
| RT. STA. 81+68.70 TO RT. STA. 88+56.00 | 687.30 | 3.0 | | 229 | 29.0 | |
| LT. STA. 81+68.70 TO LT. STA. 88+56.00 | 687.30 | 3.0 | | 229 | 29.0 | |
| RT. STA. 454+00.00 TO RT. STA. 459+53.00 | 553.00 | 4.0 | | | | 245.8 |
| LT. STA. 454+00.00 TO LT. STA. 459+53.00 | 553.00 | 4.0 | | | | 245.8 |
| RT. STA. 459+53.00 TO RT. STA. 465+55.30 | 602.30 | 4.0 | | | | 267.6 |
| LT. STA. 459+53.00 TO LT. STA. 464+47.68 | 498.00 | 4.0 | | | | 221.3 |
| RT. STA. 468+14.70 TO RT. STA. 469+00.00 | 85.54 | 4.0 | | | | 38.0 |
| LT. STA. 464+47.64 TO LT. STA. 469+00.00 | 460.00 | 4.0 | | | | 204.4 |
| RT. STA. 469+00.00 TO RT. STA. 469+30.00 | 30.00 | 4.0 TO 1.0 | | | | 8.3 |
| LT. STA. 469+00.00 TO LT. STA. 469+30.00 | 30.00 | 4.0 TO 1.0 | | | | 8.3 |
| FAP 612 (IL 103) | | | | | | |
| RT. STA. 1+57.35 TO RT. STA. 5+00.00 | 346.38 | 4.00 | | | | 154 |
| LT. STA. 1+05.10 TO LT. STA. 5+00.00 | 397.95 | 4.00 | | | | 177 |
| TOTAL | | | 342 | 458 | 101 | 1570.5 |

| AGGREGATE SHOULDER SCHEDULE | | | | | |
|--|----------------|--|---|---|--|
| LOCATION STATION TO STATION | LENGTH (FT) | AGGREGATE SHOULDERS, WIDTH (FT) | AGGREGATE SHOULDERS, TYPE B (WEDGE) (TON) | AGGREGATE SHOULDERS, TYPE B (FULL 6") (SQ YD) | |
| FAP 317 (US 24) | | | | | |
| RT. & LT. STA. 52+00.00 TO RT. & LT. STA. 81+68.70 | 2,968.70 | 3 | 338 | - | |
| RT. & LT. STA. 81+68.70 TO RT. & LT. STA. 88+56.00 | 687.30 | - | - | - | |
| RT. & LT. STA. 88+56.00 TO RT. & LT. STA. 97+30.50 | 874.50 | 3 | 100 | - | |
| STA. EQ. STA. 97+30.50 (BK) = STA. 97+73.16 (AH) | | | | | |
| RT. & LT. STA. 97+73.16 TO RT. & LT. STA. 184+77.90 | 8,704.74 | 3 | 992 | - | |
| STA. EQ. STA. 184+77.90 (BK) = STA. 184+92.93 (AH) | | | | | |
| RT. & LT. STA. 184+92.93 TO RT. & LT. STA. 309+15.00 | 12,422.07 | 3 | 1415 | - | |
| STA 309+15.00 TO STA. 420+00.00 | 11,085.00 | 3 | 1262 | - | |
| OMISSION FOR BRIDGE REMOVAL & REPLACEMENT STA. 420+00.00 TO STA. 454+00.00 | | | | | |
| STA. 454+00.00 TO STA. 459+53.00 | 553.00 | 3 | 63.0 | - | |
| RT. STA. 459+53.00 TO RT. STA. 461+12.90 | 159.90 | 4 & VARS. | - | 70.6 | |
| LT. STA. 459+53.00 TO LT. STA. 463+97.10 | 444.10 | 4 & VARS. | - | 197.4 | |
| LT. STA. 464+96.57 TO LT. STA. 469+30.00 | 433.43 | 4 & VARS. | - | 192.6 | |
| RT. STA. 469+00.00 TO RT. STA. 469+30.00 | 30.00 | VARS. | - | 13.3 | |
| FAP 612 (IL 103) | | | | | |
| RT. STA. 1+57.77 TO RT. STA. 5+00.00 | 342.23 | 4 & VARS. | - | 156.6 | |
| LT. STA. 1+05.42 TO LT. STA. 5+00.00 | 394.58 | 4 & VARS. | - | 175.5 | |
| (AREA FLOODED FROM CADD) | | | | | |
| TOTAL | | | 4170.0 | 806.0 | |

| PAVEMENT REMOVAL SCHEDULE | | | |
|----------------------------------|----------------|---------------|--------------------------------|
| LOCATION STATION TO STATION | LENGTH (FT) | WIDTH (FT) | PAVEMENT REMOVAL (SQ YD) |
| FAP 317 (US 24) | | | |
| STA. 462+93.00 TO STA. 466+55.00 | 362.00 | VARIES | 327.0 |
| TOTAL | | | 327.0 |