

**HOT-MIX ASPHALT BASE COURSE 11 1/4" SCHEDULE**

LOCATION STATION TO STATION	LENGTH (FT)	PROPOSED WIDTH (FT)	HOT-MIX ASPHALT BASE COURSE 11 1/4" (SQ YD)
FAP 317 (US 24)			
STA. 460+53.00 TO STA. 461+73.00	120.00	VAR. 0.0 TO 6.0	40.0
STA. 461+73.00 TO STA. 462+93.00	120.00	VAR. 6.0 TO 12.0	120.0
STA. 462+93.00 TO STA. 465+33.10	240.10	12.00	320.1
STA. 465+33.10 TO STA. 1+47 (IL 103)		VARIES	445.6
STA. 468+12.30 TO STA. 469+00.00	87.70	VAR. 0.0 TO 6.0	20.0
FAP 612 (IL 103)			
STA. 0+11.00 TO STA. 1+00.00	89.00	VARIES	325.2
STA. 1+00.00 TO STA. 1+24.00	24.00	VAR. 0 TO 6.0	5.5
STA. 1+47.00 TO STA. 3+06.00	159.00	VAR. 0 TO 6.0	52.6
TOTAL			1,329.0

AGGREGATE DITCH CHECKS		
LOCATION	TON	
FAP 612 (IL 103)		
STA. 2+50.0 LT.	6.0	
STA. 4+75.0 LT.	6.0	
STA. 4+75.0 RT.	6.0	
TOTAL		18.0

**MEDIAN, CONCRETE CURB, AND GUTTER SCHEDULE**

LOCATION STATION TO STATION	COMBINATION CURB AND GUTTE REMOVAL (FOOT)	COMB CC&G T B 6.24 (FOOT)	CONCRETE MEDIAN TYPE SM 4.24 (SQ FT)	COMB CC&G T M 4.06 (FOOT)
FAP 612 (IL 103)				
RT. STA. 0+18.00 TO RT. STA. 1+57.35	170.4	208.0		
LT. STA. 0+11.00 TO LT. STA. 1+05.10	65.6	127.0		
RT. STA. 0+5.85 TO RT. STA. 0+21.62			92.0	50.0
LT. STA. 0+32.38 TO LT. STA. 0+48.74			73.0	39.0
TOTAL		236.0	335.0	89.0

**PERIMETER EROSION BARRIER**

LOCATION STATION TO STATION	LENGTH (FT)	
FAP 317 (US 24)		
RT. STA. 459+53.00 TO RT. STA. 466+00.00	647.0	
RT. STA. 467+35.33 TO RT. STA. 468+50.00	115	
FAP 612 (IL 103)		
RT. STA. 0+21.73 TO RT. STA. 2+00.00	179.0	
LT. STA. 1+00.00 TO LT. STA. 1+72.49	72	
TOTAL		1,014.00

**GUARDRAIL SCHEDULE**

LOCATION STATION TO STATION	LENGTH (FT)	GUARDRAIL REMOVAL (FOOT)	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 1 SPL (TANGENT) (EACH)	GUARDRAIL MKR TYPE A (EACH)	TERMINAL MARKER DA (EACH)
FAP 317 (US 24)						
RT. STA. 322+42.00 TO STA. 326+40.00	398.00	398.00				
LT. STA. 323+20.00 TO STA. 326+68.00	348.00	348.00				
RT. STA. 322+41.00 TO STA. 326+41.00	400.00		300.00	2.00	2.00	2.00
LT. STA. 323+19.50 TO STA. 326+69.50	350.00		250.00	2.00	2.00	2.00
TOTAL		746.0	550.0	4.0	4.0	4.0

• 9RS-4, (10,11)RS-3; (10B-1)R  
•• BROWN & SCHUYLER COUNTIES