

PAINT PAVEMENT MARKING LINE - 5" SCHEDULE

STATION TO STATION	DESCRIPTION	LINE 5"		
		WHITE (FT)	YELLOW (FT)	
FAP 317 (US 24)				
LT. STA 51+65.00 TO LT. STA 61+81.28	LEFT EDGE LINE, SOLID	968	-	
STA. 51+65.00 TO STA. 61+81.28	CENTER LINE, SKIP - DASH	-	254	
RT. STA 51+65.00 TO RT. STA 61+81.28	RIGHT EDGE LINE, SOLID	904	-	
LT. STA 61+81.28 TO LT. STA 68+72.96	LEFT EDGE LINE, SOLID	692	-	
STA 61+81.28 TO STA 68+72.96	CENTER LINE LEFT, SKIP - DASH CENTER LINE SOLID	- -	173 692	
RT. STA 61+81.28 TO RT. STA 68+72.96	RIGHT EDGE LINE, SOLID	632	-	
LT. STA 68+72.96 TO LT. STA 283+94.24	LEFT EDGE LINE, SOLID	20988	-	
STA. 68+72.96 TO STA. 283+94.24	CENTER LINE, SKIP - DASH	-	5380	
RT. STA 68+72.96 TO RT. STA 283+94.24	RIGHT EDGE LINE, SOLID	20724	-	
LT. STA 283+94.24 TO LT. STA 292+12.64	LEFT EDGE LINE, SOLID	768	-	
STA 283+94.24 TO STA 292+12.64	CENTER LINE LEFT, SKIP - DASH CENTER LINE SOLID	- -	205 818	
RT. STA 283+94.24 TO RT. STA 292+12.64	RIGHT EDGE LINE, SOLID	774	-	
LT. STA 292+12.64 TO LT. STA 294+50.24	LEFT EDGE LINE, SOLID	238	-	
STA 292+12.64 TO STA 294+50.24	CENTER LINE, SKIP - DASH	-	60	
RT. STA 292+12.64 TO RT. STA 294+50.24	RIGHT EDGE LINE, SOLID	238	-	
LT. STA 294+50.24 TO LT. STA 301+41.92	LEFT EDGE LINE, SOLID	692	-	
STA 294+50.24 TO STA 301+41.92	CENTER LINE LEFT, SKIP - DASH CENTER LINE SOLID	- -	173 692	
RT. STA 294+50.24 TO RT. STA 301+41.92	RIGHT EDGE LINE, SOLID	692	-	
LT. STA 301+41.92 TO LT. STA 309+42.00	LEFT EDGE LINE, SOLID	740	-	
STA. 301+41.92 TO STA. 309+42.00	CENTER LINE, SKIP - DASH	-	200	
RT. STA 301+41.92 TO RT. STA 309+42.00	RIGHT EDGE LINE, SOLID	800	-	
LT. STA 309+42.00 TO LT. STA 393+72.00	LEFT EDGE LINE, SOLID	8160	-	
STA. 309+42.00 TO STA. 393+72.00	CENTER LINE, SKIP - DASH	-	2108	
RT. STA 309+42.00 TO RT. STA 393+72.00	RIGHT EDGE LINE, SOLID	8300	-	
LT. STA 393+72.00 TO LT. STA 402+55.00	LEFT EDGE LINE, SOLID	883	-	
STA 393+72.00 TO STA 402+55.00	CENTER LINE LEFT, SKIP - DASH CENTER LINE RIGHT, SOLID	- -	221 883	
RT. STA 393+72.00 TO RT. STA 402+55.00	RIGHT EDGE LINE, SOLID	883	-	
LT. STA 402+55.00 TO LT. STA 415+75.00	LEFT EDGE LINE, SOLID	1241	-	
STA. 402+55.00 TO STA. 415+75.00	DOUBLE CENTER LINE, SOLID	-	2640	
RT. STA 402+55.00 TO RT. STA 415+75.00	RIGHT EDGE LINE, SOLID	1091	-	
LT. STA 415+75.00 TO LT. STA 420+00.00	LEFT EDGE LINE, SOLID	425	-	
STA 415+75.00 TO STA 420+00.00	CENTER LINE, SKIP - DASH	-	107	
RT. STA 415+75.00 TO RT. STA 420+00.00	RIGHT EDGE LINE, SOLID	425	-	
OMISSION BRIDGE REMOVAL & REPLACEMENT STA. 420+00.00 TO STA. 454+00.00				
LT. STA 454+00.00 TO LT. STA 459+53.00	LEFT EDGE LINE, SOLID	553	-	
STA 454+00.00 TO STA 459+53.00	CENTER LINE, SKIP - DASH	-	139	
RT. STA 454+00.00 TO RT. STA 459+53.00	RIGHT EDGE LINE, SOLID	553	-	
		SUB - TOTALS	72364	14745
		TOTAL	87109	

SUB-BASE GRANULAR MATERIAL, TYPE A 8" SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	PROPOSED WIDTH (FT)	SUB-BASE GRAN MAT TYPE A 8" (SQ YD)
FAP 317 (US 24)			
STA. 460+53.00 TO STA. 462+93.00	240.00	VAR. 1.0 TO 13.0	186.7
STA. 462+93.00 TO STA. 465+33.00	240.00	13.00	346.7
STA. 465+33.00 TO STA. 4+00 (IL 103)		VARIES	625.5
FAP 612 (IL 103)			
STA. 0+11.00 TO STA. 1+24.00		VARIES	422.1
TOTAL			1,581.0

**PREFORMED PLASTIC PAVEMENT MARKING, TYPE B
INLAID - LETTERS AND SYMBOLS SCHEDULE**

STATION TO STATION	DESCRIPTION	WHITE (SQ FT)
INTERSECTION US 24 & IL 103		
US 24		
RT. STA 462+93.00	RIGHT TURN ARROW	15.6
RT. STA 463+88.00	RIGHT TURN ARROW	15.6
RT. STA 464+83.00	RIGHT TURN ARROW	15.6
RT. STA 465+78.00	RIGHT TURN ARROW	15.6
TOTAL		63

**RAISED REFLECTIVE PAVEMENT
MARKER REMOVAL SCHEDULE**

STATION TO STATION	QUANTITY (EACH)	
US 24		
STA. 51+70.00 TO STA. 309+15.00	322	
STA. 309+15.00 TO STA. 420+00.00	139	
OMISSION BRIDGE REMOVAL & REPLACEMENT STA. 420+00.00 TO STA. 454+00.00		
STA. 454+00.00 TO STA. 459+53.00	8	
STA. 459+53.00 TO STA. 469+30.00	22	
IL 103		
STA. 0+00 TO STA. 5+00.00	8	
TOTAL		499

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwwork\pwidot\LAUGHLINRL\dms20637\672432-ah-t-sch.dgn		DRAWN -	REVISED -
PLOT SCALE = 56.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Mar-23-2010 01:59:35PM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	*	**	196	24
CONTRACT NO. 72432				
ILLINOIS FED. AID PROJECT				

* 9RS-4, (10,11)RS-3; (10B-1)R
** BROWN & SCHUYLER COUNTIES