

SHORT-TERM PAVEMENT MARKING &  
WORK ZONE PAVEMENT MAKING REMOVAL SCHEDULE

STATION TO STATION	LOCATION	DESCRIPTION	LENGTH (FT)	QUANTITY			
				SHORT-TERM		WORK ZONE	
				WHITE (FT)	YELLOW (FT)	(SQ FT)	
US 24							
STA. 51+70.0 TO STA. 309+15.0	CENTER LINE	SKIP - DASH	25745.0	-	7724	858.1	
STA. 309+15.0 TO STA. 420+00.0	CENTER LINE	SKIP - DASH	11085.0	-	3318	369.0	
OMISSION BRIDGE REMOVAL & REPLACEMENT STA. 420+00.00 TO STA. 454+00.00							
STA. 454+00.0 TO STA. 459+53.0	CENTER LINE	SKIP - DASH	553.0	-	166	19.0	
STA. 459+53.0 TO STA. 469+30.0	CENTER LINE	SKIP - DASH	977.0	-	293	32.5	
STA. 462+93.0 TO STA. 466+33.0	LANE LINE (RT.)	SKIP - DASH	340.0	102	-	11.0	
STA. 466+73.0 TO STA. 467+50.0	ISLAND EDGE LINE (RT.)	SKIP - DASH	77.0	23	-	2.5	
IL 103							
STA. 0+00.0 TO STA. 5+00.0	CENTER LINE	SKIP - DASH	500.0	-	150	17.0	
STA. 465+81 (US 24) TO STA. 0+42	ISLAND EDGE LINE (LT.)	SKIP - DASH	100.0	30	-	3.5	
STA. 0 +78 TO STA. 467+50 (US 24)	ISLAND EDGE LINE (LT.)	SKIP - DASH	100.0	30	-	3.5	
				SUB - TOTAL			
				TOTAL		11836	1316

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE

STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	TWO-WAY AMBER (EACH)	ONE-WAY AMBER (EACH)	ONE-WAY CRYSTAL (EACH)	
US 24							
STA. 51+70.00 TO STA. 309+15.00	CENTER LINE SKIP - DASH	25745.0	1 @ 80'	322	-	-	
STA. 309+15.00 TO STA. 420+00.00	CENTER LINE SKIP - DASH	11085.0	1 @ 80'	139	-	-	
OMISSION BRIDGE REMOVAL & REPLACEMENT STA. 420+00.00 TO STA. 454+00.00							
STA. 454+00.00 TO STA. 459+53.00	CENTER LINE SKIP - DASH	553.0	1 @ 80'	8	-	-	
STA. 459+53.00 TO STA. 469+30.00	CENTER LINE SKIP - DASH	977.0	1 @ 80'	13	-	-	
RT. STA 462+93.00 TO RT. STA 466+33.00	TURN LANE LINE, SOLID	340.0	1 @ 40'	-	-	9	
RT. STA 465+81.00 TO RT. STA 466+33.00	ISLAND EDGE LINE, SOLID	52.0	1 @ 40'	-	4	-	
RT. STA 466+73.50 TO RT. STA 467+50.00	ISLAND EDGE LINE, SOLID	76.5	1 @ 40'	-	6	-	
IL 103							
STA. 0+50.00 TO STA. 3+06.00	MEDIAN LINE, SOLID DOUBLE	256.0	2 @ 40'	-	14	-	
STA. 3+06.00 TO STA. 5+00.00	CENTER LINE, SOLID	194.0	1 @ 80'	-	3	-	
				TOTAL	482	27	9
				TOTAL			
				TOTAL		518	